

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-025-20752-0000

Give All Information Completely
 Make Required Affidavit

COUNTY Clark SEC. 19 TWP. 31 RGE. 21 EXW
 Location as in quarters or footage from lines:
660' FNL & 579' FEL

Lease Owner Mesa Petroleum Co.
 Lease Name Seacat SWS Well No. 4
 Office Address P.O. Box 2009 / Amarillo, Texas 79189
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed N/A
 Application for plugging filed Verbal obtained 12-19-83
 Plugging commenced 12-20-83
 Plugging completed 12-20-83
 Reason for abandonment of well or producing formation Insufficient salt water present

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
 Producing formation N/A Depth to top _____ bottom _____ T.D. 450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	370'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from 424 feet
 to Surface feet for each plug set. Dumped 3 yds gravel from 424' to 370'. Set 30 sx
Class "A" cement from 370' to 295'. Dumped 4 yds gravel from 295' to 50'. Set 20 sx
Class "A" cement from 50' to surface. Cut off 8 5/8" csg 3' below ground and welded on
dry hole cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mesa Petroleum Co.

STATE OF TEXAS COUNTY OF POTTER, ss.
R. E. MATHIS (employee of owner) or ~~(owner)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. E. Mathis
P.O. Box 2009 / Amarillo, TX 79189
 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1983

My Commission expires: 8/22/87

XC: KCC (O+1), CEN RCDS, ACCTG, MAT CONT, RES ENG, OPS(FILE), MID CONT, PARTNERS

