

11-18

1031482

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
WICHITA STATE OFFICE BUILDING
WICHITA, KANSAS 67202

API number: 15-129-21,544 ~~6000~~

NW NE NW SEC. 26, 31 S, 41 W
4950 feet from S section line
3630 feet from E section line

Operator license #5123 Lease KU Endowment I well # 1

Operator: Pickrell Drilling Co., Inc. County Morton

Address: 110 N. Market, Ste. 205 Well total depth 5566 feet
Wichita, KS 67202 Conductor Pipe: inch @ feet
Surface pipe: 8 5/8 inch @ 1560 feet

180.90

RECEIVED
KANSAS CORP COM
NOV 24 D 1:55

Aband. Oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Cheyenne Drilling, Inc. License# 5382

Address: P O BOX 916, Garden City, KS 67846

Company to plug at: Hour: ____ Day: 18 Month: November Year: 1997

Plugging proposal received from: Duane Chisolm

Company: Cheyenne Drilling, Inc. Phone: 316-277-2062

Were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 1590' with 50 sx cement,
- 2nd plug at 690' with 25 sx cement,
- 3rd plug at 40-0' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement,
- 5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by: Steve Durrant

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 7:30 p.m. Day: 18 Month: November Year: 1997

Actual plugging report:

- 1st plug at 1680' with 50 sx cement,
- 2nd plug at 688' with 25 sx cement,
- 3rd plug at 60' with 40 sx cement,
- 4th plug to circulate rathole with 15 sx cement,
- 5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

I did[] / did not[X] observe the plugging.

Steve Durrant

(agent)
Form CP-2/3

INVOICED
DATE DEC 09 1997
INVOICE NO. 49615

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 11-5-97

State of Kansas

129-21,544-0000

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

DISTRICT # 1
SCA? Yes No

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 11 - 7 - 97
month day year

Spot NW NE NW Sec 26 Twp 31 S, Rg 41 X East West

OPERATOR: License # 5123
Name: Pickrell Drilling Company, Inc.
Address: 110 N. Market, Suite 205
City/State/Zip: Wichita, Kansas 67202
Contact Person: Bill C. Romig
Phone: 316-262-8427

4950 feet from South/North line of Section
3630 feet from East/West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5382
Name: Cheyenne Drilling, Inc.

County: Morton
Lease Name: KU Endowment I. Well #: 1
Field Name: Kinsler

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Morrow

Nearest lease or unit boundary: 330'
Ground Surface Elevation: 3375 est feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
X Gas ... Storage X Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 325
Depth to bottom of usable water: 500

Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 1550

Length of Conductor pipe required:
Projected Total Depth: 5600

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
X well ... farm pond ... other

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

DNR Permit #:
Will Cores Be Taken?: yes X no

If yes, proposed zone:
520' Alt. I Reg.

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 4/30/98

AFFIDAVIT

RECEIVED
KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101.

Quorum
Wagner
WUD DATE 11-7-97 INIT. SD
LENGTH SURFACE PLANNED - 1550-60

RESERVE PIT STATUS- REMOVE FLUID LINED
Water salt sect. bbls. when done bbls.

WTHOLED AHEAD? Y N SIZE HOLE
IRFACE PIPE 8 7/8 @ 1560 CONDUCTOR
HYDRITE T- B- ELEVATION
5566

FORMATION MISS

IN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1590 / 1680 Ft. W/ 50 SX

1/2 Base Anyh. @ Ft. W/ SX

2 1/2, 1/2 Plug @ 690 / 688 Ft. W/ 25 SX

Bottom Surface @ 60 Ft. W/ 40 SX

3 40' Plug @ 400 Ft. W/ 10 SX

T HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

TER WELL SX (Irr. Well Pond Hauling X)

CHNICIAN SD DATE 11-15-97

PE OF CEMENT 6/4 60% 991 NOV 24 P 1:55

ARTING TIME (AM/PM) DATE 11-15-97

MPLETION TIME 7:30 (AM/PM) DATE 11-18

AGENT COMPANY Allead

RECEIVED
KANSAS CORPORATION COMMISSION
11-18