

To: 100134
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

5-29 API NUMBER 15- 129-20,793-0000
C SE SW, SEC. 26, T 31 S, R 41 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

660 feet from S section line
3300 feet from E section line

Lease Name Johns B Well # 1

County Morton 182.00

Well Total Depth 5600 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1520

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address P.O. Box 49BA, Rt. 1, Tyrone, OK 73951-9731.

Company to plug at: Hour: 9:30 a.m. Day: 29 Month: 5 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

logs: 4 1/2" at 5352' w/215 sx cement, PBDT 5350, CIBP @ 2250', 2350', 3235', & 4157',

Perfs at 2176-99', FO tool @ 2283', TOC @ 1710'

1st plug pump 1 sx hulls and 20 sx cement on bottom, 2nd plug at 1550' with 50 sx cement,

3rd plug at 550' with 40 sx cement, 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 29 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2250' with 2 sx cement on top,

2nd plug spotted 20 sx cement and 2 sx hulls at 2176-1976', displaced with mud,

3rd plug spotted 50 sx cement at 1550', displaced with mud,

4th plug spotted 40 sx cement at 550', displaced with mud,

5th plug spotted 10 sx cement at 40'.

Remarks: Used common cement by Sargent & Horton. Recovered 1730' of 4 1/2" casing.
Additional description is necessary, use BACK of this form.)

I (did / XXXX XXXX) observe this plugging.

DATE JUN 05 1997

INV. NO. 48220

5-29

Signed Gary Winters
(TECHNICIAN)