

1 060840

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,794-0600

NE NE NE, SEC. 26, T 31 S, R 41 (W/E)

4770 feet from S section line

510 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Johns Well # C-1

Operator: Anadarko Petroleum Corp.

County Morton 186.88

Name & Address P. O. Box 351

Well Total Depth 5750 Morrow feet

Address Liberal, KS 67901

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1555

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address English Key Building, 333 East English, # 215, Wichita, KS 67202

Company to plug at: Hour: 4:00 am Day: 19 Month: March Year: 19 86

Plugging proposal received from Chuck Nelson

(company name) Gabbert-Jones (phone) 316-263-6209

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3365'
Anhydrite 1550'

1st plug spot the Morrow at 5002 with 40 sx cement

2nd plug to cover the Chase Group at 2176' with 75 sx cement

3rd plug 30' below the base of the surface pipe (in the Anhydrite) with 50 sx cement

4th plug at 600' with 30 sx cement

solid bridge - hulls - plug at 40' -- cement to surface

5th plug with 10 sx cement Plugging Proposal Received by Paul A. Luthi

7th plug to circulate rat hole with 15 sx cement. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 am Day: 19 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 5002' with 40 sx cement, 2nd plug at 2176' with 75 sx

cement, 3rd plug at 1585' with 50 sx cement, 4th plug at 600' with 30 sx cement, 5th &

6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1986

Remarks: Used 65/35 Pozmix 4% gel by Halliburton. CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED
(I observe this plugging.)

Signed Paul A. Luthi (TECHNICIAN)

DATE MAR 20 1986

INV. NO. 13015

3-19

FORM CP-2/3
Rev. 01-84