

1 010217

MAR 3 1987

API NUMBER 15- 129-20,849-~~6000~~

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SE, SEC. 27, T 31 S, R 41, W/E

990 feet from S section line

990 feet from E section line

Lease Name Hanke Trust Well # 1

County Morton 178.75

Well Total Depth 5500 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1494

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254

Operator: Midco Exploration, Inc.

Name & Address 200 East 1st Street, Suite 411

Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling Inc. License Number 4813

Address P.O. Box 990, Great Bend, KS 67530

Company to plug at: Hour: 7 a.m. Day: 3 Month: 3 Year: 19 87

Plugging proposal received from Bill Nelson

(company name) Mustang Drilling Inc. (phone) 316-792-6877

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3378' GL
Anhydrite 1492'

1st plug at 1480' with 50 sx-cement, 2nd plug at 740' with 50 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:15 a.m. Day: 3 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,

2nd plug at 800' with 30 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICED

(operator did not) observe this plugging.

Signed Jack Luthi (TECHNICIAN) MAR 5 1987

CONSERVATION DIVISION

Wichita, Kansas

FORM CP-2/3 Rev. 01-84

DATE 3-9-87

INV. NO. 16315

3-5-87

Handwritten initials

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 2 13 1987 month day year

API Number 15- 129-20,849-0000

OPERATOR: License # 5254 Name Midco Exploration, Inc. Address 200 E. 1st St., Suite 411 City/State/Zip Wichita, Ks. 67202 Contact Person Harvey Gough Phone 316-267-3613

NW. SE. SE. Sec. 27... Twp 31... S, Rg. 41... X West 990 Ft. from South Line of Section 990 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 4813 Name Mustang OAG, Inc. City/State Great Bend, Ks. 67530

Nearest lease or unit boundary line 990 feet County Morton Lease Name Hanke Trust Well # 1 Ground surface elevation Unknown at 3370 feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no Depth to bottom of fresh water Lower Crat Depth to bottom of usable water 425 Surface pipe by Alternate 1 X 2 Surface pipe planned to be set 1400 Conductor pipe required None Projected Total Depth 5500 feet Formation Mississippi

Well Drilled For: Well Class: Type Equipment: Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date Feb 9, 1987 Signature of Operator or Agent Harvey Gough Title Vice President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 450 feet per Alt. This Authorization Expires 8-10-87 Approved By 2-10-87

Spud 14 to 145 on 16th

MOB on 2-19-87

1520 = 8 5/8

feet/KCC No

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, size (sxs), and formation details. Includes entries for 1st, 2nd, 3rd, 4th, 5th plugs and Rathole.

NOTE: PUSHER Bill Nelson TD 5500 FORMATION Min SURFACE PIPE 8 5/8 @ 1494 ANHYDRITE 1492 ELEVATION 3370 RSL STARTING TIME & DATE 7:45 3-3 COMPLETION TIME & DATE 9:15 3-3 1st PLUG @ 1530 FT. W/ 50 SX 2nd PLUG @ 800 FT. W/ 30 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Hollidays 60/40 6 90 TECHNICIAN

STATE CORPORATION COMMISSION MAR 5 1987 CONSERVATION DIVISION Wichita, Kansas