

1050273

129-10089-0000 *R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Not Available  
*NW 1/4*, SEC. 36, T 31 S, R 41 *W/K*  
3969 N *north of (w) line* feet from *N/S* section line  
1391.8 E *East of (w) line* feet from *W/E* section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6416

Lease Name Mitchell Well # 1

Operator: Daco, Inc.

County Morton

Name & Address P. O. Drawer 3010

Well Total Depth 5700 *185.25* feet

Borger, TX 79008-3010

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1514

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Daco, Inc. License Number 6416

Address P. O. Drawer 3010, Borger, TX 79008-3010

Company to plug at: Hour: 3:00 pm Day: 28 Month: June Year: 19 84

Plugging proposal received from Jack Painter

(company name) Daco (phone) 806-273-7321

were: 5 1/2 at 5250' PBTD 5310, Perfs 5283' in Morrow 2220-2223' 2231-2235' 2240-2246

1st plug CIBP and 5 sx cement at 5250'

2nd plug CIBP and 20 sx cement at 2300'

3rd plug at 1575 with 75 sx cement

4th plug at 750' with 40 sx cement

5th plug at 40' with 10 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 6:00 pm Day: 28 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 at 5250' PBTD 5310' Perfs: 5283' 2220-2223' 2231-2235' 2240-2246

1st plug set CIBP and 5 sx cement at 5250', 2nd plug set CIBP and 20 sx cement at 2300'

3rd plug at 1575' with 75 sx cement, 4th plug at 750' with 40 sx cement, 5th plug at

40' with 10 sx cement to surface.

Don Ubel gave the plugging orders.

Remarks: They recovered 1563' of 5 1/2" casing. Used common sacked cement.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-16-84

7-6-84

JUL 06 1984

Signed

Richard W. Lacey  
(TECHNICIAN)

INV. NO. 2492

6-28

JUL 17 1984

CONSERVATION DIVISION  
Wichita, Kansas

AUG 3 1984

FORM CP-2/3  
Rev. 01-84