

1100375

TO: STATE CORPORATION COMMISSION

API NUMBER 15-025-20,048-00-00
C SW SEC. 11, T 35 S, R 25 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME THEIS "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY CLARK

198.25

OPERATOR LICENSE # 9228

WELL TOTAL DEPTH 6100 FEET

OPERATOR: MARLIN OIL CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 6084' WITH 200 SX

NAME AND PO BOX 14630 SURFACE CASING: SIZE 8 5/8" @ 502' WITH 675 SX

ADDRESS OKLAHOMA CITY, OK 73113-0630 CONDUCTOR CSG: SIZE 30" @ 135'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SARGENT'S CASING PULLING SERVICE LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67905-0506

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 27 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM KIRBY

(COMPANY NAME) SARGENT'S CASING PULLING SERVICE (PHONE) 316-624-7455

WERE: PERFS AT 5648-57, 5245-5300, 4547-4550

CIBP @ 5730'. 1ST PLUG PLUG OFF BOTTOM PERFS WITH 200# HULLS & 25 SX CEMENT. 2ND PLUG SPOT 50 SX CEMENT AT 1050'. 3RD PLUG SPOT 50 SX CEMENT AT 550'. 4TH PLUG SPOT 10 SX CEMENT FROM 40' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 27 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT _____

CIBP @ 5730'. 1ST PLUG PLUG OFF BOTTOM PERFS WITH 200# HULLS & 25 SX CEMENT. 2ND PLUG SPOT 50 SX CEMENT AT 1050'. 3RD PLUG SPOT 50 SX CEMENT AT 550'. 4TH PLUG SPOT 10 SX CEMENT FROM 40' TO 0'.

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2800' OF 4 1/2" CASING. CONSERVATION DIVISION
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING

INVOICE
DATE 8/3/00
1060307

SIGNED Steve Klumart
(TECHNICIAN) FORM CP-2/3