

To: 1041139  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-151-20,288-0001  
NW NE NW, SEC. 23, T 28 S, R 12 W/E  
4950 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30128  
Operator: Kenneth S. White  
Name  
Address 200 E. 1st, #405  
Wichita, KS 67202

Lease Name Chitwood Well # 1  
County Pratt 153.47  
Well Total Depth 4722 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gressel Oil Field Service Inc. License Number 3004  
Address P.O. Box 438, Haysville, KS 67060

Company to plug at: Hour: 11:30 a.m. Day: 29 Month: 12 Year: 19 95

Plugging proposal received from Ed Gressel  
(company name) Gressel Oil Field Service Inc. (phone) 316-463-5161

logs: 5 1/2" at 4696' w/250 sx cement, PBSD 3600', Perfs at 4587-90, 4565-68, 4457-74, 4253-56, 3965-67, 3730-38, 3512-15', CIBPs at 4400, 4050, & 3600'

1st plug set CIBP at 3480' and dumped 2 sx cement on top through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 4 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3480' and dumped 2 sx cement on top with dump  
bailer,

2nd plug pumped 300 lbs. hulls and 4 sx gel; big hole in surface pipe. Shut down to  
wait on rig..

1/4/96 (no witness) loaded hole with gel and spotted plugs through tubing:  
3rd plug at 700' with 50 sx cement, 4th plug at 340' with 50 sx cement, 5th plug at 40' with  
10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1834' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

and (if possible) observe this plugging.

**INVOICED**  
DATE JAN 23 1996  
INV. NO. 44704  
1-4

Signed Stephen J. Pfeiffer  
(TECHNICIAN)