

1 060944

4-6-87

15-025-20216-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilling completion date 6/26/78

NE NE NE, SEC. 18, T 31 S, R 21 WXX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Lease Name Scheib Well # 1-18

Operator: Oneok Exploration Company

County Clark 182.81

Name & Address

Well Total Depth 5625 feet

Box 784

Conductor Pipe: Size feet

Great Bend, KS 67530

Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 6 Month: 4 Year: 19 87

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 5265' Perf. at 5370' w/wire line, perfs at 5180-84' Elevation 2150'

1st plug pump 1 sx hulls and 25 sx cement-stop plug at 4550'.

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3 p.m. Day: 6 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls, 25 sx cement - stopped plug at 4550',

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

Remarks: Recovered 3600' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 4-8-87

INV. NO. 16531

4-6

Signed Paul A. Luthi (TECHNICIAN)

APR

8 1987

FORM CP-2/3 Rev. 01-84

Handwritten signature/initials