

1 060943

4-6-87 15-025-26271-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion date 11/5/79

NE NW NE, SEC. 18, T 31 S, R 21 W/E  
4680 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

1900 feet from E section line

Operator: Oneok Exploration Company

Lease Name Scherb Well # 2-18

Name: Box 784

County Clark 169.78

Address: Great Bend, KS 67530

Well Total Depth 5224 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 6 Month: 4 Year: 1987

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 5223' PBTD 5210' Perfs at 5156-8' Elevation 2110'GL

1st plug pump 1 sx hulls and 20 sx cement - stop plug at 4550',

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:30 p.m. Day: 6 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls, 20 sx cement - stopped plug at 4550',

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 1000 psi and shut in 400 psi.

Remarks: Recovered 3800' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(date ~~4-8-87~~) observe this plugging.

DATE 4-8-87

Signed Paul A. Luthi (TECHNICIAN) APR 8 1987

INV. NO. 16530  
4-6