

1 090134

10-18

140

API NUMBER 15- 025-20,368 -0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NE NE SE, SEC. 18, T 31 S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT

2130 feet from S section line  
560 feet from E section line

Operator License # 4824

Lease Name Scheib Well # 1

Operator: Mesa Operating Ltd. Partnership  
Name &

County Clark 173.87

Address P.O. Box 2009  
Amarillo, TX 79189

Well Total Depth 5350 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 664

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 1 p.m. Day: 18 Month: 10 Year: 19 91

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 5275' w/125 sx cement, Perfs at 5183-99'

1st plug pump 2 sx hulls and 20 sx cement over perfs,

2nd plug at 1100' with 50' sx cement,

3rd plug at 700' with 50' sx cement,

4th plug at 40' with 10' sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 18 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement over perfs,

2nd plug pulled to 1100' and spotted 50 sx cement,

3rd plug pulled to 700' and spotted 50 sx cement,

4th plug pulled to 40' and spotted 10 sx cement.

Cement circulated.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 22 1991

CON DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargents. Recovered 4400' of 4 1/2" casing 10.5#.

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 11-6-91

INV. NO. 33627  
10-18