

1 030812

6-5-87

API NUMBER 15-025-20,527-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW SW, SEC. 109, T 31 S, R 21 W/E

990 feet from S section line

4290 feet from E section line

Lease Name Seacat Well 10-19

TECHNICIAN'S PLUGGING REPORT

Operator License # 4824

County Clark 173.23

Operator: Mesa Operating Limited Partnership

Name & Address P.O. Box 2009

Well Total Depth 5330 feet

Amarillo, TX 79189

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 674'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated SW supply well

Plugging Contractor Pool Well Service Company License Number 7874

Address P.O. Box 998, El Reno, OK 73036

Company to plug at: Hour: 12 p.m. Day: 5 Month: 6 Year: 19 87

Plugging proposal received from Don Hall

(company name) Pool Well Service (phone) 405-262-6262

were: 5 1/2" at 5329' Perfs at 2465-3075' Elevation 2056' GL TOC 1500'

1st plug set CIBP at 3970' with 2 sx cement on top,

2nd plug set CIBP at 2375' with 2 sx cement on top,

3rd plug spot 30 sx cement on stub, 4th plug spot 50 sx cement at 611-711',

5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3 p.m. Day: 5 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3970' with 2 sx cement on top,

2nd plug set CIBP at 2375' with 2 sx cement on top,

3rd plug pump 30 sx cement on stub,

4th plug pump 50 sx cement at 611-711', JUN 9 1987

5th plug pump 10 sx cement at 0-40'. CONSERVATION DIVISION Wichita, Kansas

Remarks: Used Class H cement by B.J. Titan. Recovered 1420' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-9-87

Signed Steve Durrant (TECHNICIAN)

INV. NO. 17201

6-5