

1 030811

6-4-87

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-025-20,509-0000  
NW NW SW, SEC. 19, T 31 S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT

2400 feet from S section line  
4950 feet from E section line

Operator License # 4824

Lease Name Seacat Well # 9-19

Operator: Mesa Operating Limited Partnership  
Name & Address: P.O. Box 2009  
Amarillo, TX 79189

County: Clark 172.25  
Well Total Depth 5300 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 667

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pool Well Servicing Company License Number 7874

Address P.O. Box 998, El Reno, OK 73036

Company to plug at: Hour: 1 p.m. Day: 4 Month: 6 Year: 1987

Plugging proposal received from Don Hall

(company name) Pool Well Servicing Company (phone) 405-262-6262

were: 4 1/2" at 5277' PBDT 5205' Perfs at 5109-24' Elevation 2061'GL

1st plug set CIBP at 5000' with 2 sx cement on top, 2nd plug circulate mud and pump 50 sx cement, 3rd plug pump 50 sx cement at 720', 4th plug pump 10 sx cement at 33-0'.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 4 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5000' with 2 sx cement on top,

2nd plug circulate mud and pump 50 sx cement, @ 2700'

3rd plug pump 50 sx cement at 720',

4th plug pump 10 sx cement at 33-0'.

COMMISSION  
JUN 9 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used Class H cement by B.J. Titan. Recovered 2725' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

Signed Steve Stewart  
(TECHNICIAN)

DATE 6-9-87

INV. NO. 17202