

6-8-87

To: 1 050910
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,776-00-00

SE NE SE, SEC. 19, T 31 S, R 21 W/E

1350 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4824

Lease Name Seacat SWS Well # 5

Operator: Mesa Operating Limited Partnership
Name & Address: P.O. Box 2009
Amarillo, TX 79189

County Clark 139.75

Well Total Depth 4300 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 653

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Salt water supply well

Plugging Contractor Pool Well Servicing Company License Number 7874

Address P.O. Box 998, El Reno, OK 73036

Company to plug at: Hour: 12 p.m. Day: 8 Month: 6 Year: 19 87

Plugging proposal received from Don Hance

(company name) Pool Well Servicing Company (phone) 405-262-6262

were: 5 1/2" at 4300' PBTD 4256' Perfs at 4128-46, 4170-88' Elevation 2115' GL TOC 2050'

1st plug set CIBP at 4050' with 2 sx cement on top.

2nd plug pump 40 sx cement at 1140',

3rd plug pump 50' sx cement at 700',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 8 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4050' with 2 sx cement on top,

Circulated hole with mud, spotted plugs through casing.

2nd plug at 1140' with 40 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 40' with 15 sx cement.

Remarks: Used Class H cement by B.J. Titan. Recovered 1980' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED

STATE CORPORATION COMMISSION

JUN 11 1987

INVOICED

Observe this plugging.

DATE 6-12-87

Signed Richard W. Lacey (TECHNICIAN) CONSERVATION DIVISION Wichita, Kansas

INV. NO. 17227