

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20240-00-00
Spot: CSWSW Sec/Twnshp/Rge: 20-31S-21W
660 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: MOORE Well Number: 1-20
County: CLARK Total Vertical Depth: 5400 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 656 WITH 650 SX CMT
Production: Size 4.5 feet: 5390 WITH 250 SX CMT
Liner: Size _____ feet:
17401

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2000 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Revd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (316) 886-5665

Proposed Plugging Method: PERFORATE AT 3965' THROUGH TUBING & CASING. 1ST PLUG MIX AND PUMP 50 SX 60/40 POZMIX 2% GEL 3% CC. LOAD HOLE AND TEST PLUG. 2ND PLUG PERFORATE AT 1000' AND PUMP 40 SX CMT. WAIT ON CMT FOR HOUR. 3RD PLUG PERFORATE AT 600'. CIRCULATE CMT TO SURFACE WITH 200 SX CMT. CEMENT CIRCULATED.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/19/2000 2:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 5356'. PERFS AT 5162-5180'. 2 3/8" TUBING STUCK AT 340' DUE TO ELECT CABLE. PERFORATE AT 3965' THROUGH TUBING & CASING. 1ST PLUG MIX AND PUMP 50 SX 60/40 POZMIX 2% GEL 3% CC. LOAD HOLE AND TEST PLUG. 2ND PLUG PERFORATE AT 1000' AND PUMP 40 SX CMT. WAIT ON CMT FOR HOUR. 3RD PLUG PERFORATE AT 600'. CIRCULATE CMT TO SURFACE WITH 200 SX CMT. CEMENT CIRCULATED.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Steve Durrant
(TECHNICIAN)

*Invoice #
61771*

APR 17 2001

Form CP-2/3

MP