

1070130

TO: STATE CORPORATION COMMISSION

API NUMBER 15-025-20,679 ~~6850~~
70'W C NW SEC. 20, T 31 S, R 21 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1250 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FRANCIS WELL # 3-20

TECHNICIAN'S PLUGGING REPORT

COUNTY CLARK 174.85

OPERATOR LICENSE # 4058

WELL TOTAL DEPTH 5380 FEET

OPERATOR: AMERICAN WARRIOR

PRODUCTION CSG: SIZE 5 1/2" @ 5360' WITH 1425 SX

NAME AND PO BOX 399

SURFACE CASING: SIZE 8 5/8" @ 764' WITH 450 SX

ADDRESS GARDEN CITY, KS 67846

ABANDONED OIL WELL GAS WELL INPUT WELL ~~BE 20, 27, 29~~ SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187 MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 11 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 5200-08

SAND BACK TO 5100' AND 5 SX CEMENT WITH DUMP BAILER. 1ST PLUG SPOT 10 SX GEL AND 50 SX

CEMENT AT 819'. 2ND PLUG SPOT 40 SX CEMENT AT 400'. 3RD PLUG SPOT 10 SX CEMENT AT 0-40'.

GOOD CIRCULATION THROUGHOUT JOB.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:15 PM DAY: 11 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

SAND BACK TO 5100' AND 5 SX CEMENT WITH DUMP BAILER. 1ST PLUG SPOT 10 SX GEL AND 50 SX

CEMENT AT 819'. 2ND PLUG SPOT 40 SX CEMENT AT 400'. 3RD PLUG SPOT 10 SX CEMENT AT 0-40'.

GOOD CIRCULATION THROUGHOUT JOB.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1440' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED

[Handwritten Signature]
(TECHNICIAN)

DATE 5/22/00

FORM CP-2/3

INV. NO. 61766

CONSERVATION DIVISION
Wichita, Kansas

APR 19 2000
[Handwritten Initials]

RECEIVED
STATE CORPORATION COMMISSION