

To: 1090508  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-23 API NUMBER 15- 025-21,120-0000  
160' E & 15' N  
S/2 NW SE, SEC. 21, T. 31 S, R. 21 W/E

1665 feet from S section line

1820 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Lease Name Strodtman Well # 1 1/2

Operator: Robinson Oil Company

County Clark

Name & Address 300 W. Douglas, Ste. 420

Well Total Depth 5250 170,635 feet

Wichita, KS 67202

Conductor Pipe: Size 13 3/8 feet 60

Surface Casing: Size 8 5/8 feet 635

Abandoned Oil Well  Gas Well  Input Well  SMD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour:            Day: 23 Month: 11 Year: 1994

Plugging proposal received from Joe Levingston

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1100' with 40 sx cement, 2nd plug at 660' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour:            Day: 23 Month: 11 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 1100' with 40 sx cement,

2nd plug at 660' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOICED** (if not) observe this plugging.

DATE 12-9-94

INV. # 41882

11-23 FEB 16 1995

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 08 1994

CONSERVATION DIVISION  
WICHITA, KS

FOR KCC USE:

15-025-21,120-0000 SKID RIG JOB

FORM C-1 7/93

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 11/13/94

DISTRICT #

Well Name

State of Kansas NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well.

Foot 160' E and 15' N of Sec 21, Twp 31., S, Rq. 21, East West

Expected Spud Date 11/13/94 month day year

OPERATOR: License # 5038 Name: Robinson Oil Company Address: 300 W. Douglas, Suite 420 City/State/Zip: Wichita, KS 67202 Contact Person: Bruce M. Robinson Phone: (316) 262-8794

CONTRACTOR: License #: 5929 Name: Duke Drilling Co., Inc.

Well Drilled For: Well Class: Type Equipment: Oil Enh Rec Infield X Mud Rotary Gas Storage X Pool Ext. Air Rotary OAWD Disposal Wildcat Cable Seismic # of Holes Other

If OAWD: old well information as follows:

Operator: Well Name: MA Comp. Date: Old Total Depth

1665 feet from South North line of Section 1820 feet from East West line of Section IS SECTION X REGULAR IRRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side) County: Clark

Lease Name: Stephens Well #: 11/2 Field Name: Lexington East

Is this a Prorated/Spaced Field? yes X, no

Target Formation(s): Morrow

Highest lease or unit boundary: 575

Ground Surface Elevation: 2061 feet MSL

Water well within one-quarter mile: yes X, no

Public water supply well within one mile: yes X, no

Depth to bottom of fresh water: 150

Depth to bottom of usable water: 180

Surface Pipe by Alternate: X, 1, 2

Length of Surface Pipe Planned to be sets: (660) 200!

Length of Conductor pipe required: None

Projected Total Depth: 5280

Formation at Total Depth: Mississippian

Water source for Drilling Operations: well farm pond X, other

Directional, Deviated or Horizontal wellbore? yes no If yes, true vertical depth: Bottom Hole Location:

Will Cores Be Taken? yes X, no If yes, proposed zones

200' Alt. I Req.

Exp. 5/14/95

AFFIDAVIT

Pusher Joe SPUD DATE 11-13-94 INIT. SM LENGTH SURFACE PLANNED 600 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2 @ 6 3/4 CONDUCTOR 60' 1338 ANHYDRITE T- B ELEVATION TD 5250 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 1100 Ft. W/ 40 SX 1/2 Base Anyh. @ Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 660 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SM DATE 11-22-94 TYPE OF CEMENT 6040 6-1e STARTING TIME (AM/PM) DATE COMPLETION TIME (AM/PM) DATE 11-27-94 CEMENT COMPANY Allied