

To: 1031454 6-22  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-025-21,164-0000  
C S/2 NE, SEC. 22, T 31 S, R 21 W/E  
1980 feet from NE section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5038  
Operator: Robinson Oil Company  
Name & Address 300 W. Douglas, Ste. 420  
Wichita, KS 67202

Lease Name Berryman A Well # 2  
County Clark 169.33  
Well Total Depth 5210 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 607

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company License Number 5418  
Address P.O.Box 1389, Great Bend, KS 67530.

Company to plug at: Hour: 4 a.m. Day: 22 Month: 6 Year: 19 97

Plugging proposal received from Vince Schrepel  
(company name) Allen Drilling Company (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 1330' with 50 sx cement, 2nd plug at 990' with 50 sx cement,  
3rd plug at 630' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6 a.m. Day: 22 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1330' with 50 sx cement,  
2nd plug at 990' with 50 sx cement,  
3rd plug at 630' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOICED** observe this plugging.

DATE JUL 03 1997  
INV. NO. 48488

Signed Steve Durrant  
(TECHNICIAN)

RECEIVED  
KANSAS  
CORP COM  
JUL 10 1997

FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 6-3-97  
DISTRICT # 1  
SGA? Yes  No

State of Kansas  
NOTICE OF INTENTION TO DRILL 025-21,164-0000  
Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date May 30 1997  
month day year

Spot S<sub>1/2</sub> NE Sec 22 Twp 31 S, Rg 21 East  West

OPERATOR: License # 5038  
Name: Robinson Oil Company  
Address: 300 W. Douglas, Suite 420  
City/State/Zip: Wichita, KS 67202  
Contact Person: Bruce M. Robinson  
Phone: 262-6734

1980 feet from South / North line of Section  
1320 feet from East / West line of Section  
IS SECTION  REGULAR  IRREGULAR?  
(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 5414 5418  
Name: Allen Drilling Company

County: Clark  
Lease Name: Berryman A Well #: 2  
Field Name: Lexington East  
Is this a Prorated/Spaced Field? yes  no   
Target Formation(s): Mississippian  
Nearest lease or unit boundary: 1320  
Ground Surface Elevation: 2077 feet MSL  
Water well within one-quarter mile: yes  no   
Public water supply well within one mile: yes  no   
Depth to bottom of fresh water: 150'  
Depth to bottom of usable water: 180'  
Surface Pipe by Alternate: X 1  2   
Length of Surface Pipe Planned to be set: 650'  
Length of Conductor pipe required: will set 40'  
Projected Total Depth: 5280'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
 well  farm pond  other

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec  Infield  Mud Rotary  
 Gas ... Storage  Pool Ext. ... Air Rotary  
... OAWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
If OAWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? yes  no   
If yes, true vertical depth: \_\_\_\_\_  
Bottom Hole Location: \_\_\_\_\_

Will Cores Be Taken?: no  
If yes, proposed zone: \_\_\_\_\_

Exp. 11/29/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with the provisions of the Kansas Code, Chapter 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

1. Notify the appropriate district office prior to starting of well.

Sitka - 2E

RECEIVED  
KANSAS CORP COMM  
JUN 26 12:10

Pusher Marvin Unger

SPUD DATE 6-2-97 INIT. \_\_\_\_\_  
LENGTH SURFACE PLANNED 650'

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 60 @ 607 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- B- ELEVATION \_\_\_\_\_

TD 5210 FORMATION Mississipi

RAN PIPE @ SX DV TOOL SX ALT IF DONE SX Y N

Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Ing./Council @ 1330 Ft. W/ 50 SX  
990  
Anhydrite Base @ 1330 Ft. W/ 50 SX  
700' Ft. W/ 50 SX  
630  
1/2 Base Anyh. @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Bottom Surface @ 030 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 1 1/2 SX MOUSE HOLE W/ 1 1/2 SX

WATER WELL X Clear SX (Irr. Well \_\_\_\_\_ Fond \_\_\_\_\_)  
Hauling \_\_\_\_\_

TECHNICIAN SD DATE 6-20-97

TYPE OF CEMENT 6/4 G Pot

STARTING TIME 4:00 AM (AM/PM) DATE 6-22-97

COMPLETION TIME 6:00 AM (AM/PM) DATE 6-22-97

CEMENT COMPANY Allen