

1-030226

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9668

Operator: Imperial Oil & Gas, Inc.
Name & Address 720 Fourth Financial Center
Wichita, KS 67202

API NUMBER 15- 025-20,825-0006

C SE SE SW, SEC. 26 ; T 31 S, R 21 W
330 FSL feet from N SE-Corner of XX section line
2970 FEL feet from W SE-Corner of XX section line

Lease Name Dammier Well # 1-26County ClarkWell Total Depth 5235 170.14 feetConductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 603 600Abandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereinafter indicated Plugging Contractor Eagle Drilling, Inc. License Number 5380Address Box 8609, Wichita, KS 67208Company to plug at: Hour: 6:00 pm Day: 12 Month: July Year: 19 84Plugging proposal received from Butch Steinert(company name) Eagle (phone) 316-682-5513

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1020' with 50 sx cement

2nd plug at 660' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Uremont
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 8:15 pm Day: 12 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 660' with 50 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton(If additional description is necessary, use BACK of this form for Wichita, Kansas)

I N V O I C E D (did not) observe this plugging.

DATE 7-27-84INV. NO. 2207 7-12Signed Steve Uremont
(TECHNICIAN)