

1 060883

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Operator: ONEOK Exploration Company
Name & Address P.O. Box 871
Tulsa, OK 74102

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 KS State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 10:15 p.m. Day: 2 Month: 10 Year: 19 86

Plugging proposal received from Bob Hough

(company name) ONEOK (phone) 918-588-7700

were: To fill hole with heavy mud and spot cement through drill pipe Elevation 2000' GL
Anhydrite 1160'

1st plug pump 100 sx red dyed cement on logging tool and drop dry bit upside down on
top of cement

2nd plug at Base Anhydrite with 50 sx cement

3rd plug at 30' Base surface pipe with 50 sx cement

4th plug at 40-0' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 3 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 5126' with 100 sx red dyed cement

2nd plug dropped 7 7/8 bit upside down in hole and pushed to 4685' on solid cement

3rd plug at 1160' with 50 sx red dyed cement

4th plug at 660' with 50 sx cement, 5th plug at 40-0' with 10 sx cement

6th plug to circulate rathole with 15 sx cement.

Two-stage radioactive logging tool left in hole on bottom.

Remarks: Used 60/40 Pozmix 6% gel (red dyed) by Halliburton.

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

OCT 8 1986

INVOICED

DATE 10-9-86

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 15122
10-3

(see rules on reverse side)

Starting Date 9/15/86
month day year

API Number 15- 025-20,961-0000

OPERATOR: License # 4548
Name ONEOK Exploration Company
Address P. O. Box 871
City/State/Zip Tulsa, OK 74102
Contact Person Clark Southmayd
Phone (918) 588-7700

SE SE Sec. 26 Twp. 31 S, Rg. 21 East
660 Ft. from South Line of Section
660 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
County Clark
Lease Name Valentine Well # 1-26
Ground surface elevation feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water 200
Depth to bottom of usable water 225
Surface pipe by Alternate: 1X 2
Surface pipe planned to be set 600
Conductor pipe required
Projected Total Depth 5200 feet
Formation Morrow

CONTRACTOR: License # 5302
Name Red Tiger Drilg. Co.
City/State Wichita, Kansas

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

certify that well will comply with K.S.A. 55-101, et seq, plus occasionally studding hole to KCC specifications.

Date Sept. 10, 86 Signature of Operator or Agent Title Manager, Drilg. & Prod.

For KCC Use: Wm. Clark Southmayd

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 20
This Authorization Expires 3-12-87 Approved By 9-12-86

Spud 9-16-86

all cond.

205
ZCA/KCC

Set 600 + 7A a 4 E. N 2 mile
638 with junction

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Bob Hough called
1 stage tool in hole.

Anhydrite
1st plug @ Stone Crowley 1100 feet depth with 50 sxs of Class H
2nd plug @ 630 feet depth with 50 sxs of Class H
3rd plug @ 40-40 feet depth with 10 sxs of Class H
4th plug @ feet depth with sxs of
5th plug @ feet depth with sxs of
2) Rathole with 15 sxs (b) Mousehole with 10 sxs

PUSHER	Ross Crawford
TD	5' 2 1/2' FORMATION
SURFACE PIPE	8 1/8 @ 640
ANHYDRITE	ELEVATION
STARTING TIME & DATE	
PLETION TIME	
1st PLUG	@ Base Nuy FT. W/ 50 SX
2nd PLUG	@ 30' B SFT. W/ 50 SX
3rd PLUG	@ 40-0 FT. W/ 10 SX
4th PLUG	@ FT. W/ SX
RAT HOLE CIRCULATED	W/ 15 SX
MOUSE HOLE CIRCULATED	W/ SX
WATER WELL PLUGGED	W/ Hand-Poured SX
CEMENT COMPANY	
TECHNICIAN	640 lbs 60% grar-

100 -
125
225