

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20942-00-01  
Spot: SWSW Sec/Twnshp/Rge: 13-33S-35W  
672 feet from S Section Line, 4527 feet from E Section Line  
Lease/Unit Name: CAMPBELL 1-A Well Number: 2  
County: STEVENS Total Vertical Depth: 6463 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: PO BOX 4358  
HOUSTON, TX 77210

Conductor Pipe: Size 16 feet: 60 210.05  
Surface Casing: Size 8.625 feet: 1750 WITH 700 SX CMT  
Production: Size 5.5 feet: 6448 WITH 970 SX CMT  
Liner: Size feet:

Well Type: HI UIC Docket No: Date/Time to Plug: 07/11/2002 12:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. 1ST PLUG AT 1760' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG  
Date/Time Plugging Completed: 07/11/2002 2:30 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 5674'. PERFS AT 2690-2718 & 2744-66'. DV TOOL @ 4013' WITH 500 SX CMT. ON 07/09/02: PUMP 400# HULLS WITH 25 SX CMT FOR BOTTOM PLUG. DISPLACE WITH MUD, PRESSURED TO 700 PSIG. HOLE LOADED. ON 07/11/02: PULL OUT OF HOLE WITH 5 1/2" CASING. 1ST PLUG RUN IN HOLE WITH 2 3/8" TUBING TO 1800' (INSIDE 5 1/2") PUMPED 30 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600' & PUMP 60 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40', LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED  
SEP 03 2002  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1239' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed

Jim Holland PERT#  
(TECHNICIAN)

INVOICED AUG 14 2002

DATE

9-4-02

INV. NO.

2003060472

Form CP 2/3