

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Crescent Petroleum Corporation API NO. 15-175-20,580-00 00
 ADDRESS 1660 Lincoln, Suite 2526 COUNTY Seward
Denver, Colorado 80264 FIELD Liberal Light
 **CONTACT PERSON Reed A. Wacker LEASE Light Estate
 PHONE 316-624-1986


PURCHASER _____ WELL NO. 1
 ADDRESS _____ WELL LOCATION _____

1320 Ft. from North Line and
 1980 Ft. from West Line of
 the SEC. 11 TWP. 35S RGE. 32W

DRILLING CONTRACTOR NRG Drilling, Inc.
 ADDRESS P.O. Box 1157
Liberal, Kansas 67901

PLUGGING CONTRACTOR Midwest Casing Pulling Service
 ADDRESS Box F, Sublette, Kansas 67877

TOTAL DEPTH 6350' PBDT _____
 SPUD DATE 1-9-82 DATE COMPLETED 3-17-82
 ELEV: GR 2743 DF KB 2754'



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

KCC
 KGS

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	23#	1610'	HLC Class H	600 200	1/4# flocele & 2% cc 3% cc
Production	7-7/8"	4 1/2"	10.5#	5653'	Class H/Poz A	150	18% salt, 3/4% CFR-2

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3-1/8" csg. gun	5525-5530'

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
Az 500 gal. 7 1/2% MCA acid & disp. w/24 bbl. 2% KCl water	5525-5530'
Az 500 gal. 15% MCA acid & disp. w/28 bbl. 2% KCl water	
Az 2000 gal. 15% HCL acid commingled w/1000 scf/bbl. N ₂	

TEST DATE:		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
PTA			
RATE OF PRODUCTION PER 24 HOURS	OIL	Gas	Water
	bbls.	MCF	bbls.
Disposition of gas (vented, used on lease or sold)		Producing Interval (ft)	

* The person who can be reached by phone regarding any questions concerning this application.
 The well was tested initially by the Commission on 3-17-82. The well is located in a Basic Order Pool.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 25 1982
 CONSERVATION DIVISION
 Wichita Kansas
 3-25-82

Name of lowest fresh water producing stratum Ogallala Depth 280'
 Estimated height of cement behind pipe Surface

WELL LOG

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Ran DST #1 had wk. bto thru 1st. & 2nd. op.; rec. 3' drlg. mud; IH 2887#, IFP 160 to 289#, ISIP 257#, FFP 289 to 289#, FSIP 289#, FH 2887#.	5892'	6050'	Council Grove	2960'
			Lansing	4600'
			Marmaton	5310'
Ran DST #2 had a wk. bto thru 1st. & 2nd. op.; NGTS, rec. 330' GCM & 90' sli OCM; IH 2808#, IFP 82 to 98#, ISIP 1229#, FFP 148 to 180#, FSIP 1572#, FH 2808#.	5496'	5547'	Morrow	5950'
PTA 3/17/82; Well plugging record on file.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Kansas, COUNTY OF Seward SS,

Reed A. Wacker OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:


THAT HE IS Agent FOR Crescent Petroleum Corporation OPERATOR OF THE Light Estate LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 17th DAY OF March 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Reed A. Wacker

SUBSCRIBED AND SWORN TO BEFORE ME THIS 24th DAY OF March 19 82

A. J. Parnell
 NOTARY PUBLIC



MY COMMISSION EXPIRES: