

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,555

LEASE NAME Hamm

WELL NUMBER 1-24

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 24 TWP. 28 RGE. 12 (W or (W))

COUNTY Pratt

Date Well Completed 2-16-85

Plugging Commenced 2-17-85

Plugging Completed 2-17-85

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947 Pratt, Kansas 67124

PHONE#(316) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4560

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Well was plugged with 125 sxs 60/40 poz, 2% gel, 3%cc as follows: 600' - 80' sxs 40' - 10 sxs with solid bridge; rathole - 15 sxs; mousehole - 10 sxs; water well - 10 sxs. Job by Sun Cementing, ticket #206716. Plug down at 4am on February 17, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P.O. Box 329 Pratt, Kansas 67124

STATE OF KANSAS COUNTY OF PRATT, ss.

Arnie Little

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little


(Address) P.O. Box 329 Pratt, KS 67124

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 85



Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Hamm #1-24
 C SW SE Sec. 24-28S-12W
 Pratt County, Kansas
 Commenced: 2-5-85
 Completed: 2-17-85
 API #15-151-21,555
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	218	Sand	Ran 7 joints (303') new, 24#, 8 5/8" surface casing. Set at 322' with 225 sxs Common, 2% gel, 3% cc. Job by Buie, ticket #3587. Cement did circulate. Plug down at 4 a.m. on February 6, 1985.
218	611	Red Bed	
611	1057	Red Bed, Shale	
1057	1300	Shale	
1300	4560	Lime, Shale	
		T.D.	

RTD 4560'

Plugged well with 125 sxs 60/40 poz, 2% gel, 3% cc as follows: 600'-80 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; mousehole-10 sxs; water well-10 sxs. Job by Sun Cementing, ticket #206716. Plug down at 4 a.m. on February 17, 1985. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss.
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT



Mary L. Tjaden
 NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSION

MAR 08 1985

CONSTRUCTION DIVISION
 W. of Kansas

My Commission Expires:
3/22/88