


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 27 Twp. 28 Rge. 12 (E) (W)

Location as "NE/CNWSW" or footage from lines \_\_\_\_\_  
Lease Owner Raymond Oil Co., Inc.  
Lease Name Chitwood A#4 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7/29/69 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 8/8/69 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4459 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	329'	none
				5 1/2"	4437'	1980'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4459', ran sand to 4400', ran 5 sacks of cement. Shot pipe at 3162', 3003', 2880', 2678', 2512', no gain in tension. Spotted 40 barrels oil and 62 barrels water, worked pipe. Plug was at 1000', fished out plug, shot pipe at 2430', 2362', 2260', 2168', 2074', 1980', worked pipe loose and pulled 63 joints. Set 10' rock bridge at 270' and ran 4 sacks of cement. Bailed hole to 260', ran 21 more sacks of cement. Mudded hole to 40', set 10' rock bridge and ran 10 sacks of cement.

PLUGGING COMPLETE.


RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

Suggested and sworn to before me this 18th day of August 19 69



My commission expires 2/15/71

Margaret Melcher  
Notary Public.

Chitwood "B" No. 1

NE NW SE  
Sec. 27-28S-12W  
Pratt County, Kansas

Contractor: R. C. Patton Drilling Company

Started: November 28, 1944

Finished: December 19, 1944

LOG

Clay	0 - 45	
Shale and Shells	45 - 60	
Sand and Gravel	60 - 270	
Red Bed and Shells	270 - 331	8-5/8" @ 327' w/175 sacks
Red Bed and Shells	331 - 400	
Red Bed and Shells	400 - 725	
Shale and Shells	725 - 980	
Shale and Shells	980 - 1295	Straight hole test @ 1000' - OK
Shale and Shells	1295 - 1630	Straight hole test @ 1500' - OK
Shale and Shells	1630 - 1765	
Lime	1765 - 1810	
Lime and Shale	1810 - 1865	
Lime and Shale	1865 - 1955	
Shale	1955 - 1965	
Lime and Shale	1965 - 2075	Straight hole test @ 2000' - OK
Lime and Shale	2075 - 2135	
Shale	2135 - 2155	
Lime and Shale	2155 - 2255	
Lime and Shale	2255 - 2330	
Shale and Lime	2330 - 2425	
Lime and Shale	2425 - 2485	
Lime and Shale	2485 - 2515	Straight hole test @ 2500' - OK
Broken Lime and Shale	2515 - 2550	
Shale and Shells	2550 - 2670	
Shale and Shells	2670 - 2795	
Lime and Shale	2795 - 2875	
Shale and Shells	2875 - 2880	
Lime	2880 - 2918	
Lime	2918 - 2980	
Lime	2980 - 3030	Straight Hole test @ 3000' - OK
Broken Lime	3030 - 3110	
Broken Lime	3110 - 3175	
Lime	3175 - 3240	
Lime	3240 - 3370	
Lime	3370 - 3475	
Lime	3475 - 3560	
Lime	3560 - 3625	Straight hole test @ 3500' - OK
Lime and Shale	3625 - 3656	
Shale and Lime	3656 - 3725	
Lime and Shale	3725 - 3760	
KC Lime	3760 - 3780	
Lime	3780 - 3825	
Lime	3825 - 3865	
Lime	3865 - 3920	
Lime	3920 - 4050	Straight hole test @ 4000' - OK
Lime and Shale	4050 - 4077	
Lime	4077 - 4110	
Lime and Shale	4110 - 4170	
Sandy Lime and Shale	4170 - 4217	
Lime	4217 - 4255	
Lime and Shale	4255 - 4295	
Shale	4295 - 4338	
Lime and Chert	4338 - 4373	
Lime	4373 - 4437	
Sand	4437 - 4439	R. T. D. 5-1/2" @ 4437' w/250 sacks

STATE OF KANSAS)  
COUNTY OF PRATT) ss.

I, Vernon Hayes, do hereby certify that the above is a true and accurate log of the Chitwood "B" Well No. 1, located NE NW SE Sec. 27-28S-12W, Pratt County, Kansas.

*Vernon Hayes*  
Superintendent

Subscribed to and sworn before me this 4th day of May, 1954.  
My Commission Expires August 29, 1955

*Wm. S. ...*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 29 1960  
CONSERVATION DIVISION  
Wichita, Kansas