


15-151-10450-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section List

Pratt County. Sec. 23 Twp. 28S Rge. 12 (E) (W)
Location as "NE/CNWSW" or footage from lines SWSW NE
Lease Owner Raymond Oil Co., Inc.
Lease Name Chitwood I-11 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2/9/73 19
Plugging completed 2/13/73 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4418 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	350	none
				5 1/2"	4412	2775

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 4390' and ran 5 sacks of cement. Loaded casing with water, shot pipe at 2800' and spotted 40 barrels oil, pulled 90 joints of 5 1/2" casing. Set rock bridge at 250' and ran 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1973
02-26-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor VOTH CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 19th day of February, 1973

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975



Margaret Melcher
Notary Public.

SW SW NE
Sec. 23-T28S-R12W
Pratt County, Kansas

Barker No. 3

Contractor: Corbett-Barbour Drlg Co.

Started: May 10, 1944

Finished: June 13, 1944

Drillers Log

Surface soil & sand	0- 225
Red bed & shells	750 10-3/4" @ 350' w/200 sacks
shells & shale	780 Straight hole test @ 500' - OK
Anhydrite	820
Shells & shale	945
Lime, shells & shale	1660 Straight hole test @ 1500' - OK
Lime	2040
Sandy lime & shale	2065
Shale & lime shells	2160
Lime	2475
Lime & shale	2505
Lime	2705
Broken lime & shale	2810
Shale & lime	2855
Lime	3015
Broken lime & shale	3090
Broken lime	3275
Lime	3425
Broken lime	3475
Lime & shale	3626
Shale & lime	3690
Lime & shale	3820 Straight hole test @ 3750' - OK
Lime	3860
Lime & shale	3930
Lime	3955
Lime & shale	3977
Lime	4086 Straight hole test @ 4000' - OK
Lime & shale	4200
Lime & chert	4204
Lime	4216 4216' - 4193 SLM
Lime	4227
Shale & lime	4253
Lime & shale	4270
Lime	4272
Lime & shale	4283
Sand	4292
Lime & shale	4347
Lime	4356
Lime & chert	4362
Lime & shale	4368
Lime	4387
Lime & chert	4404
Lime & shale	4418 5 1/2" @ 4412' w/400 sacks R.T.D.

STATE OF KANSAS)
COUNTY OF PRATT) ss.

I, Vernon Hayes, do hereby certify that the above log is true and correct to the best of my knowledge and belief.

Subscribed ~~to~~ and sworn to before me this 23rd day of June, 1954.

Vernon Hayes

Don Daubert
Notary Public

My commission Expires August 29, 1955.