

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market,
Wichita, Kansas 67202.

WELL PLUGGING RECORD

Pratt County, Sec. 23 Twp. 28 Rge. 12W (E) (W)

Location as "NE/CNWKSWK" or footage from lines. NW NE NE
Lease Owner Raymond Oil Co., Inc.
Lease Name Chitwood #12 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2/8/71 19
Plugging completed 2/11/71 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4427 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	344	none
				5 1/2"	4420	2920'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 4350', set 5 sacks of cement.
Loaded hole with water, shot pipe at 2932', spotted 40 barrels
of oil, worked pipe loose and pulled 90 joints. Set rock
bridge 340' and ran 40 sacks of cement. Mudded hole to 40',
and ran 15 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
KNIGHT CASING PULLING CO., INC.

Name of Plugging Contractor
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS
(Address)

Subscribed and Sworn to before me this 18th day of February, 1971

My commission expires

2/15/75

Notary Public.

Barker No. 4

NW NE NE

Sec. 23-28S-12W

Pratt County, Kansas

Contractor: Corbett - Barbour Drilling Company

Started: July 25, 1945

Finished: August 22, 1945

Drillers Log

surface sand & shells	0-75
sand	135
shale & shells	350
red bed, shale & shells	618
anhydrite	630
red bed	640
red bed & shells	995
shale & shells	1505
salt & shale	1615
shale & shells	1675
sandy lime	1735
lime	1990
lime & shale	2035
lime	2130
lime & shale	2385
lime	2425
lime & shale	2670
lime broken	2825
lime & shale	2880
lime	3155
lime & shale	3245
lime	3435
lime & shale	3515
broken lime	3615
lime	4070
lime & shale	4125
lime	4176
lime & shale	4198
shale & chert	4215
lime & shale	4254
shale & lime	4333
lime	4361
lime & shale	4410
shale & lime	4420
lime	4423
4423 Rot. TD 4421 SIM	
sand	4427 TD

10-3/4" @ 344' with 250 sacks
slope test at 500', okay

slope test at 1500', okay

slope test at 2000', okay

slope test at 2500', okay

slope test at 3000', okay

slope test at 3500', okay

slope test at 4000', okay

Plugged Back to 4399'
5-1/2" @ 4420' with 400 sacks

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1970
CONSERVATION DIVISION
Wichita, Kansas

I, Bruce E. Roll, do hereby certify that the foregoing log is true and correct to the best of my knowledge and belief.

Bruce E. Roll

Subscribed and sworn to before me this 20th. day of March, 1957.

Maile J. Lombar
Notary Public

My commission Expires, September 19, 1959