


STATE OF KANSAS  
 STATE CORPORATION COMMISSION

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 212 No. Market  
 Wichita, Kansas 67202

NORTH

### WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County, Sec. 23 Twp. 28 Rge. 12 (E) (W)  
 Location as "NE/CNW/SW" or footage from lines  
 Lease Owner Raymond Oil Co., Inc.  
 Lease Name Chitwood H#8 Well No.  
 Office Address Wichita, Kansas 67202  
 Character of Well (completed as Oil, Gas or Dry Hole)  
 Date well completed 19  
 Application for plugging filed 19  
 Application for plugging approved 19  
 Plugging commenced 1/28/70 19  
 Plugging completed 2/3/70 19  
 Reason for abandonment of well or producing formation depleted  
 If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
 Producing formation Depth to top Bottom Total Depth of Well 4500 Feet  
 Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	300	none
				5 1/2"	4493'	2701'

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 10 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4500', ran sand to 4375' and ran 5 sacks of cement. Loaded hole with water, shot pipe at 3093', 2971', 2852', pumped load of water at 1200 lb. pressure, pumped 40 barrels oil and 73 barrels water, worked pipe to 25" tension, shot pipe at 2700', worked pipe loose and pulled 86 joints. Bailed hole to 250', set 10' rock bridge and ran 25 sacks of cement. Mudded to 40', set 10' rock bridge and ran 10 sacks of cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor KNIGHT CASTING PULLING CO., INC.  
 Address CHASE, KANSAS


STATE OF KANSAS, COUNTY OF RICE, ss.  
 NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
 CHASE, KANSAS  
 (Address)

Subscribed and sworn to before me this 4th day of February, 1970

My commission expires 2/15/71  
 Margaret Melcher  
 Notary Public.



0	240	Surface clay and sand
240	300	Red Bed and lime shells
300	375	Red Rock
375	1116	Shale and Shells
1116	1516	Shale and lime shells
1516	1500	Salt
1500	1776	Shale & Shells
1776	1665	Lime and Shale
1665	1995	Lime
1995	2035	Shale & lime streaks
2035	2153	Broken Lime
2153	2200	Lime and Shale
2200	2265	Broken Lime
2265	2349	Lime
2349	2410	Shale
2410	2550	Shale & Lime
2550	2650	Shale
2650	2665	Sand
2665	2775	Lime
2775	2780	Shale
2780	2830	Shale & Shells
2830	2845	Lime
2845	2975	Lime and Sand
2975	3065	Shale and Shells
3065	3165	Lime, Shale
3165	3210	Lime
3210	3225	Sand
3225	3260	Shale
3260	3275	Broken Lime
3275	3295	Shale
3295	3335	Lime
3335	3405	Shale
3405	3445	Lime
3445	3485	Lime, Shale
3485	3515	Lime and Sand
3515	3610	Broken Lime
3610	3700	Lime
3700	3725	Shale and Sand
3725	3780	Lime, broken
3780	3832	Lime (Whipstock)
3832	4040	Hard Lime
4040	4073	Shale & Lime
4073	4097	Lime
4097	4125	Shale and Lime
4125	4167	Lime
4167	4165	Lime hard
4165	4166	Cherty Mississippi Lime
4166	4183	Lime, hard
4183	4201	Hard Cherty Lime
4201	4252	Shale and Lime
4252	4272	Lime
4272	4295	Shale
4295	4392	Viola Lime
4392	4429	Simpson Sand
4429	4453	Dolomite
4453	4473	Gray Shale
4473	4494	Shale
4494	4500	Arbuckle
4500		Total Depth

PLUGGING BACK RECORD

Cement plug not drilled  
Completed Depth

4500 4460 L.W.P.B.T.D.  
4460  
L.W.P.D. 4385

RECORD OF FISHING JOBS & DRILLING BY  
STUCK DRILL PIPE

At 3950' stuck the drill pipe. Could not get loose, pulled pipe in two 28 stands down. Could not fish drill pipe out. Set whipstock at 1639' and drilled by to 3769' where drill pipe stuck again, back off drill pipe at top of drill collar. Could not fish balance out of hole. Started new hole at 1700' and drilled to 4500' where pipe was run and cemented at 4493'.

Formation tops as noted from samples by  
W. D. Henderson, Geologist

3685	Top Brown Lime
3700	Top E. C. Lansing Lime Slight stain 3825-3935. Oolitic Zone 3800-3910 - Oolitic Zone 3925-35. Very slight staining 3990-4030.
4147	4247 Mississippi Lime (cherty
4247	4295 Kinderhook
4295	4392 Viola Lime
4392	4395 Simpson Shale (three cores were taken from 4390-4399)
4395	4429 Simpson Sand (well saturated sand, possibly 10% Dolomite)
4429	4436 Simpson Shale, then back into Eady Dolomite, probably carrying water
4493	Top Arbuckle Lime, slight staining.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas