

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pratt County, Sec. 23 Twp. 28 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW SE

Lease Owner Raymond Oil Co., Inc.

Lease Name Chitwood G#11

Well No.

Office Address Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 10/15/69 19

Plugging completed 10/24/69 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren

Producing formation Depth to top Bottom Total Depth of Well 4429 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	300	none
				5 1/2"	4397'	2445'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods or means used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4429', ran sand to 4385', mixed and dumped 5 sacks of cement. Shot pipe at 3194', spotted 40 barrels of oil behind pipe. Worked pipe at no gain, pumped 80 barrels of water trying to push oil further up hole. Pumped 4 sacks mud, 2 sacks hulls, spotted 30 barrels of oil behind pipe. Shot pipe at 3076', pumped in 80 barrels of water, shot pipe at 2906', 2738', 2606', 2437', worked pipe loose and pulled 58 joints of 5 1/2" range 3 pipe. Bailed fluid down to 260', set 10' rock bridge and dumped 25 sacks of cement. Mudded on hole, finished mudding hole and dumped 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1969

2/15/71

My commission expires

Notary Public.

PAGE NO

Auth: 7-0352

FORM NO. 176 - PAGE 1 - 500 7-44 TONEY

Location 330' N & E SW cor. NW SE

Remarks _____

[illegible]