

15-151-10461-60-60

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Pratt County, Sec. 23 Twp. 28 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW NW  
Lease Owner Raymond Oil Co., Inc.  
Lease Name Chitwood J#8 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 8/23/72 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 9/5/72 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4481 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	308	none
				5 1/2"	4470	2433'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 4200' and ran sand and dumped 5 sacks of cement.  
Loaded hole, shot pipe at 3193', spotted oil that was in casing behind pipe. Shot pipe at 2817', 2625', 2435', pulled 76 joints.  
Bailed fluid to 240', set rock bridge from 240 to 230' and dumped 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 13 1972


CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
NOEL J. KNIHHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1972



My commission expires \_\_\_\_\_

[Signature]  
Notary Public.

Lion Oil and Refining Company  
El Dorado, Arkansas

Chitwood Well No. 3

NE SW NW  
NW-Corner SE/4, -NW/4, Sec. 23,  
Twp. 28, Range 12, Pratt  
County, Kansas.

Contractor: The R. W. Rine Drilling Company  
Commenced: October 15, 1943      Completed: November 19, 1943

<u>LOG</u>	
Clay, Sand, & Shale	Top- 230
Shale & Sand	230- 265
Red Bed	265-575 8 3/4" casing cemented at 308'
Red Bed & Shale	575-975
Shale & Shells	975-1690
Lime & Shale	1690-1890
Lime	1890-1985
Lime & Shale	1985-2200
Broken Lime	2200-2275
Lime & Shale	2275-2350
Shale	2350-2815
Shale & Lime	2815-2995
Shale	2995-3035
Shale & Lime	3035-3515
Broken Lime	3515-3695
Shale	3695-3702
Lime	3702-4062
Lime & Shale	4062-4143
Chert	4143-4159
Shale & Chert	4159-4206
Lime	4206-4220
Shale	4220-4270
Lime	4270-4293
Chert	4293-4330
Chert, Lime & Shale	4330-4351
Lime & Chert	4351-4368
Sandy Shale	4368-4370
Sand	4370-4430
Shale	4430-4440
Shale & Lime	4440-4474 5 1/2" casing cemented at 4474' Total Depth 4474'

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 22 1972  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas )  
County of Barton) ss

I, Clyde W. Goddard do hereby certify that the above is a true and complete log of the Chitwood Well No. 3, located in the NW Corner of the SE/4 of the NW/4 of Section 23, Township 28, Range 12, in Pratt County, Kansas.

Clyde W. Goddard

Sworn to and subscribed before me this 20 day of November, 1943.

Ralph Murphy County Clerk  
By Joeth Harris, Deputy

My commission expires Jan 8 - 1945