

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Morton County, Sec. 16 Twp. 33 Rge. 43W (E) (W)

Location as "NE/CNW%SW%" or footage from lines 330' N & 330' E of Center Section

Lease Owner Terminal Facilities, Inc.

Lease Name Ryman

Well No. A-1

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-22-1954 19

Application for plugging filed 1-25-1954 19

Application for plugging approved 1-26-1954 19

Plugging commenced 1-27-1954 19

Plugging completed 2-13-1954 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R.J. Phillippe

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3300 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka	Water	3170	3192	8-5/8"	606	None
"	"	3034	3058	5 1/2"	3294	951'
"	"	2902	3004			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 150 sacks of common cement down 5 1/2" casing to 2200# pressure with plug stopping at 2775'; Reclaimed 951' of 5 1/2" casing; the hole was filled with Hvy. rotary mud to 20' of surface and then cement to 4' of ground level at which point the 8-5/8" casing was cut off and a steel cap welded on.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco well servicing company

Address Borger, Texas

STATE OF Kansas, COUNTY OF Seward, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. Anderson*
Box 70, Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of Feb., 19 54

My commission expires 5-23-1957

J. T. Mahoney
Notary Public.

24-2675-B 2-52-20M

PLUGGING
FILE SEC 16 T 33 R 43W
BOOK PAGE 10 LINE 4

2-17-54