

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-095-20,501-0000

LEASE NAME Garrison

WELL NUMBER #1

2228 Ft. from (S) Section Line

592 Ft. from (E) Section Line

SEC. 24 TWP. 29 RGE. 8 (E) or (W)

COUNTY Kingman

Date Well Completed \_\_\_\_\_

Plugging Commenced 5/2/96

Plugging Completed 5/3/96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Woolsey Petroleum Corporation

ADDRESS 107 N. Market Wichita

PHONE# (316) 886-5606 OPERATORS LICENSE NO. 5506

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/17/96 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Toronto Depth to Top 3238' Bottom 3242' T.D. 4221'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Miss-4211-4215	Water	surf	248	8 5/8"	248'	-0-
Toronto 3238-3242	Water	surf	4226	4 1/2	4220	2693

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Sand over perforations to 3159' - Dump 5 sax cement w/bailer. Cut csg @ 2693' - Dump 35 sax 60/40 poz mix from 1253' to 1120'. Mud from 1120' to 838'. 35 sax from 838' to 708'. Mud from 708' to 303'. 90 sax cement from 303' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum Corporation


STATE OF Kansas COUNTY OF Barber, ss.

Carl W. Durso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Durso

(Address) \_\_\_\_\_

KANSAS CORPORATION COMMISSION SUBSCRIBED AND SWORN TO before me this 5th day of May, 1996



Caren L. Winchell  
Notary Public

MAY 09 1996

My Commission Expires: 6-21-99

CONSERVATION DIVISION  
WICHITA, KS

Form CP-4  
Revised 05-88