

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 13 Twp. 29S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner O. A. Sutton
Lease Name Van Gieson Well No. 1
Office Address 407 Insurance Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 15 1962
Application for plugging filed August 15 1962
Application for plugging approved August 15 1962
Plugging commenced August 15 1962
Plugging completed August 15 1962
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Justus
Producing formation Depth to top Bottom Total Depth of Well 4522 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	212	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole. Filled with mud 4522-180'; set plug at 180' with 1/4 sack hulls and 20 sacks cement. Plug #2 @ 35' with 1/4 sack hulls and 10 sacks cement. Plugged at 8:30 p.m.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Renfro Drilling Company
Address 316 Insurance Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. B. Krider (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. B. Krider
407 Insurance Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of August, 1962

My commission expires June 28, 1966

Jean S. Taylor
Notary Public.



Van Gieson #1 - O. A. Sutton
C. SE NW Section 13-29S-8W
Kingman County, Kansas

Date Commenced - August 3, 1962
Date Completed - August 15, 1962
Elevation - 1562 K.B.
Casing - 212' of 8-5/8" with 175 sacks of cement

DRILLERS LOG FOR WELL #1

212 - 355	Red Bed
355 - 1240	Shale/Shells
1240 - 1435	Lime/Shale
1435 - 1550	Shale/Lime
1550 - 1690	Lime
1690 - 1875	Lime/Shale
1875 - 2030	Lime/Shale
2030 - 2275	Lime/Shale
2275 - 2510	Shale/Lime
2510 - 2635	Shale/Lime
2635 - 2790	Lime/Shale
2790 - 2920	Lime/Shale
2920 - 3045	Lime/Shale
3045 - 3225	Lime/Sandy Shale
3225 - 3357	Shale/Lime
3357 - 3395	Lime/Shale
3395 - 3455	Lime
3455 - 3530	Lime
3530 - 3605	K. C./Lime
3605 - 3682	Lime/K.C.
3682 - 3720	Lime/K.C.
3720 - 3791	K.C./Lime
3791 - 3791	D.S.T. #1
3791 - 3868	Lime
3868 - 3935	Lime
3935 - 4015	Lime
4015 - 4082	Shale/Lime
4082 - 4100	Shale/Lime
4100 - 4140	Conglomerit
4140 - 4149	Miss
4141 - 4149	D.S.T. #2
4149 - 4220	Miss
4220 - 4237	Miss/Lime
4237 - 4275	Miss/Lime
4275 - 4312	Miss/Lime
4312 - 4240	Miss/Lime
4340 - 4408	Miss/Lime
4408 - 4445	Miss/Lime
4445 - 4472	Shale
4472 - 4486	Viola
4486 - 4522	Viola
4522 -	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1962
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
SEDGWICK COUNTY)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my ability and according to the records of this office.

RENFRO DRILLING COMPANY
By Eae H. Renfro

Subscribed and sworn to before me this 17th day of August 1962

By Belva J. Adams
My Commission expires December 11, 1965