


15-095-00048-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 9 Twp. 29 S Rge. 8 (E) 8 (W)
Location as "NE/CNW%SW%" or footage from lines C NW NW
Lease Owner Musgrove Drilling Company
Lease Name SCHUMAN Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 10-28-61 1961
Application for plugging filed verbally - 10-28-61 1961
Application for plugging approved verbally - 10-28-61 1961
Plugging commenced 10-28-61 1961
Plugging completed 10-28-61 1961
Reason for abandonment of well or producing formation: Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4610 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	266'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy mud to 240'
Set 1st plug at 240' w/28 sx cement plus 1/4 sk hulls
Filled hole w/ heavy mud to 40'
Set 2nd plug at 40' w/ 10 sx cement plus 1/4 sk hulls

STATE CORPORATION COMMISSION
NOV 3 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Drilling Company
Address 801 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Emil E. Bowers (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 61

My commission expires June 16, 1963

Leah Faye Hefke
Leah Faye Hefke Notary Public.



CONTRACTOR'S WELL LOG

COMPANY: Musgrove Drilling Company
 CONTRACTOR: Musgrove Drilling Company
 FARM: SCHUMAN #1
 LOCATION: C NW NW Sec. 9-29S-8W
 Kingman County, Kansas
 COMMENCED: October 13, 1961
 COMPLETED: October 28, 1961

0	266	Surface soil
266	850	Shale & red bed
850	1805	Shale & lime
1805	1952	Lime
1952	3075	Lime & shale
3075	3154	Lime
3154	3522	Lime & shale
3522	3843	Lime
3843	3891	Lime & shale
3891	3943	Lime
3943	4135	Lime & shale
4135	4213	Lime, shale & chert
4213	4248	Cherty lime and shale
4248	4294	Lime
4294	4326	Lime and chert
4326	4570	Lime
4570	4610	Sand & shale
	4610	Rotary Total Depth

Set 8-5/8" surface casing at 266' w/200 sacks cement

DRY & ABANDONED

ELEVATION: 1688 D. F.
 1691 K. B.

WELEX ELECTRIC LOG TOPS:

Heebner	3274'	(-1583)
Toronto	3287'	(-1596)
Douglas	3304'	(-1613)
Brown Lime	3508'	(-1817)
Lansing	3515'	(-1824)
B. Kansas City	3945'	(-2254)
Mississippi	4199'	(-2508)
Viola	4510'	(-2819)
Simpson	4555'	(-2864)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 8 1961
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the SCHUMAN #1, C NW NW Section 9-29-8W, Kingman County, Kansas, as reflected by the files of Musgrove Drilling Company.

Emil E. Bowers
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of November, 1961.

Leah Faye Hefke
 Leah Faye Hefke, Notary Public