

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Kingman County, Sec. 7 Twp. 29S Rge. (E) 8W (W)

Location as "NE/CNW/SW" or footage from lines NE NW  
Lease Owner Rex & Morris Drilling Company  
Lease Name Goetz 'B' Well No. 1  
Office Address P.O. Box 334, El Dorado, Kansas 67042  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-1 19 72  
Application for plugging filed 5-1 19 72  
Application for plugging approved 5-1 19 72  
Plugging commenced 5-1 19 72  
Plugging completed 5-1 19 72  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. Russel Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4565 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	284'	8-5/8"	284'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fluid to 270', plug, 25 sx cement;  
Fluid to 40', plug, 20 sx cement;  
Two sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 4 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor D N B DRILLING, INC.  
Address 737 First National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF \_\_\_\_\_, ss.  
M. F. BEAR (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. F. Bear  
737 First Nat'l Bk Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 72

My commission expires August 25, 1972

Ella Priess

Notary Public.

DRILLERS' LOG

REX & MORRIS DRILLING COMPANY  
 No. 1 Goetz 'B'  
 NE NW, Sec. 7-29S-8W  
 Kingman County, Kansas

Elev: 1702 R.B.

Commenced: 4-21-72  
 Completed: 5-1-72

Surface Casing: 284.16' of  
 8-5/8" cemented w/250 sx  
 cement, 3% cc. 4-22-72

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 291
Shale	291 - 1160
Shale & Lime	1160 - 1475
Lime & Shale	1475 - 2393
Sand	2393 - 2415
Lime & Shale	2415 - 3514
Shale	3514 - 3534
Lime	3534 - 4345
Lime & Shale	4345 - 4500
Lime	4500 - 4545
Sand	4545 - 4565 T.D.

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 4 - 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*M. F. Bear*  
 M. F. BEAR

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 3rd day of May, 1972.

My Commission Expires:  
 August 25, 1972

*Ella Priess*  
 Ella Priess, Notary Public