


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

KINGMAN County. Sec. 7 Twp. 29s Rge. 8w (#) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner PETROLEUM, INC.
Lease Name GOETZ "D" Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JUNE 12 19 58
Application for plugging filed JUNE 13 19 58
Application for plugging approved JUNE 12 19 58
Plugging commenced JUNE 12 19 58
Plugging completed JUNE 12 19 58
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRED W. HAMPEL, PRETTY PRAIRIE, KANSAS
Producing formation Depth to top Bottom Total Depth of Well 4520 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	246'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUD UP WITH HEAVY MUD TO 250' FOLLOWED BY A WOODEN PLUG AND 1/3 SACK# HULLS, PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ON TO PLUG, MUD UP TO 30' FOLLOWED BY A WOODEN PLUG AND 1/3 SACK HULLS, CEMENT TO BASE OF WELL CELLAR WITH 10 SACKS CEMENT.

6-25-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 23RD day of JUNE, 19 58

My commission expires 11/12/58
 Notary Public.

PLUGGING
FILE SEC 7 T. 29 R. 8w
BOOK PAGE 7 LINE 45

WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 7 T. 29S R. 8W

FARM GOETZ "D" NO. 1

LOC. SE, SE, SE


TOTAL DEPTH 4520'

COUNTY KINGMANOCO. KANSAS

COMM. May 28, 1958

COMP. June 12, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 252' W/225 sax.

ELEVATION 1685' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Surface clay
253	Sand & shale
700	Red bed
740	Red bed, anhydrite w/streaks sand
1630	Shale & shells
2440	Lime & shale
2700	Shale & lime
2875	Shale w/lime streaks
2985	Shale & lime
3135	Shale & broken lime
3285	Shale & lime
3510	Shale, sand w/streaks lime
3581	Shale & lime
3648	Lime & shale
3975	Lime
4080	Lime & shale
4135	Lime
4168	Lime & shale
4214	Shale & lime
4234	Lime & chert
4286	Chert
4305	Lime & chert
4330	Cherty lime
4360	Lime & shale
4420	Lime
4491	Shale & lime
4520	Lime & shale
4520	T. D.

State of KANSAS }
County of BARTON } ss:

PLUGGING
FILE SEC. 7 T. 29 R. 8W
BOOK PAGE 107 LINE 45

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Goetz "D" well

Verne A. Morris

Subscribed and sworn to before me this 19th day of June 19 58

My Commission Expires: November 12, 1958

Grandenburg
NOTARY PUBLIC