

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 26 Twp. 30S Rge. (E) 6 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW  
Lease Owner Rains & Williamson Oil Co.  
Lease Name Shore Well No. 1  
Office Address 1425 Wichita Plaza Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed May 29 1966  
Application for plugging filed May 29 1966  
Application for plugging approved May 29 1966  
Plugging commenced May 29 1966  
Plugging completed May 29 1966  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4584 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	260'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st Plug @ 250' w/25 sx.  
2nd Plug @ 40' w/10 sx.  
2 sx. in rat hole

RECEIVED  
STATE CORPORATION COMMISSION

JUN - 8 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30 Inc.  
Address 200 North Main, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains  
1425 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 1966

My commission expires March 3, 1970

Mary J. Brown  
Mary J. Brown Notary Public.

15-095-30073-0000


KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Rains & Williamson Oil Company  
FARM Shore NO. 1

SEC. 26 T. 30S R. 6W  
LOC. C NE SW

TOTAL DEPTH 4584  
COMM. 5/15/66 COMP. 5/29/66  
SHOT OR TREATED  
CONTRACTOR H-30, Inc.  
ISSUED

COUNTY Kingman  
KANSAS



CASING  
20 10  
15 8 -5/8" @ 260 w/225 sx. cement  
12 6  
13 5

ELEVATION 1361 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	25
Red Bed	70
Red Bed & Shale	260
Red Bed	320
Shale & Shells	1045
Shale & Lime	1430
Lime	1600
Lime & Shale	1800
Shale & Lime	3067
Shale, Lime & Sand	3517
Lime	3785
Lime & Shale	3855
Lime	3907
Lime & Shale	4108
Lime, Shale & Chert	4129
Chert & Lime	4138
Lime & Chert	4266
Chert & Lime	4375
Lime & Chert	4417
Shale & Lime	4520
Lime & Shale	4534
Sand	4584
Rotary T. D.	4584

ELECTRIC LOG TOPS:

Heebner	2971	-1610
Douglas	3068	-1707
Stalnaker	3302	-1941
Kansas City	3518	-2157
Base Kansas City	3773	-2412
Cherokee	3974	-2613
Mississippi	4109	-2748
Kinderhook	4412	-3051
Viola	4524	-3163
Simpson	4535	-3174
Log T. D.	4582	-3221
Rotary T. D.	4584	-3223

RECEIVED  
STATE CORPORATION COMMISSION  
JUN - 8 1966  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

Merle Britting  
Merle Britting

STATE OF KANSAS )  
                          )ss  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 6th day of June, 1966.

Maxine Lampe  
Maxine Lampe - Notary Public

My Commission Expires:  
December 27, 1967