


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 25 Twp. 30S. Rge. (E) 6 (W)
Location as "NE/CNW/SW" or footage from lines SW NE NE
Lease Owner National Oil Co., Inc.
Lease Name Drouhard Well No. 1
Office Address 200 West Douglas, Suite 550, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 2, 1973
Application for plugging filed January 2, 1973
Application for plugging approved January 2, 1973
Plugging commenced January 2, 1973
Plugging completed January 2, 1973
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4585 Feet
Show depth and thickness of all water, oil and gas formations.

| OIL, GAS OR WATER RECORDS | | | | CASING RECORD | | |
|---------------------------|---------|------|----|---------------|--------|------------|
| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
| | | | | 8-5/8" | 293' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Mudded up with heavy mud to 290 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of February, 1973

[Signature]
Betty Brandt
Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: National Oil Co., Inc. DRILLING COMMENCED: December 20, 1972
 200 W. Douglas, Suite 550
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: January 2, 1973
 505 Union Center
 Wichita, Kansas 67202

CASING RECORD: 7 Jts. 293' 8-5/8" cemented with 250 sacks LOCATION: Drouhard No. 1
 SW NE NE
 Section 25-30S-6W
 Kingman County, Kansas

| | | | |
|-------------|------------------------|-------------|--------------------|
| 0 - 30 | Sand | 3577 - 3730 | Lime |
| 30 - 293 | Shale & shells | 3730 - 4070 | Lime & shale |
| 293 - 865 | Red bed & shale | 4070 - 4098 | Shale & lime |
| 865 - 1325 | Shale, lime & shells | 4098 - 4115 | Lime |
| 1325 - 2575 | Lime & shale | 4115 - 4190 | Chert & lime |
| 2575 - 2756 | Lime | 4190 - 4413 | Lime |
| 2756 - 2860 | Shale & sand | 4413 - 4530 | Shale |
| 2860 - 2960 | Shale & sandy lime | 4530 - 4546 | Lime & chert |
| 2960 - 3150 | Lime & shale | 4546 - 4560 | Dolomite |
| 3150 - 3425 | Shale, sandy with lime | 4560 - 4585 | Sand |
| 3425 - 3520 | Shale & lime | 4585 | Rotary Total Depth |
| 3520 - 3577 | Lime & shale | | |

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 22 1973
 CONSERVATION DIVISION
 Wichita, Kansas

By John Graves
 President

STATE OF KANSAS)
)
 SEDGWICK COUNTY,) ss.

Subscribed and sworn to before me, a Notary Public, this 20th of February, 1973.

My commission expires:

Betty Brandt
 Betty Brandt Notary Public

May 9, 1975