

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail and Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Kingman County, Sec. 21 Twp. 30S Rge. 6 (E) W (W)

Location as "NE/CNW/SW" or footage from lines Apx. C SE NE

Lease Owner Bell Oil Company

Lease Name Boileau Well No. 1

Office Address 562 Wetmore Ct., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed 4/23 19 72

Application for plugging filed 4/23 19 72

Application for plugging approved 4/23 19 72

Plugging commenced 4/23 19 72

Plugging completed 4/23 19 72

Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G.R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	278'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 300' 50 sx cement
1/2 sx hulls & plug @ 40' w/
15 sx cement to surface,
2 sx in rathole.

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company

Address 1720 Wichita Plaza, Wichita, Ks.


STATE OF Kansas, COUNTY OF Sedgwick ss.

Jim Farrice (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Farrice
1720 Wichita Plaza, Wichita, Ks.
(Address)

Subscribed and sworn to before me this 26th day of April, 19 72



Virginia K. Albert
Notary Public.

DRILLERS LOG

No. 1 Boileau

CASING RECORD:

8 5/8" @ 278'
w/200 sx cement

COMPANY: Bell Oil Company

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: April 7, 1972

COMPLETED: April 23, 1972

DESCRIPTION:

Apx. C SE NE
21-309-6W
Kingman County,
Kansas

TOTAL DEPTH: 4500'

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	15	
Surface Clay & Shale	15	221	
Shale	221	280	
Shale & Shells	280	909	
Lime & Shale	909	2755	
Lime	2755	3110	
Lime & Shale	3110	3340	
Lime	3340	3758	
Lime & Shale	3758	3809	
Lime	3809	4385	
Lime & Shale	4385	4450	
Lime	4450	4500	

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1972
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 25th day of April, 1972.



Virginia H. Albert
Notary Public

My Commission Expires:
7-23-74