


15-095-01086-0000

Give All Information Completely
Make Required
Mail or Deliver to
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 19 Twp. 30 S Rge. 6 W (X) (W)
Location as "NE/CNW/SW" or footage from lines SW NE SE
Lease Owner Clinton Oil Company (formerly Gulf Oil Corp.)
Lease Name Reid Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 24 19 61
Application for plugging filed November 2 19 67
Application for plugging approved November 3 19 67
Plugging commenced 11/9/67 19
Plugging completed 11/14/67 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production October 31 19 67
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justice
Producing formation Mississippi Depth to top 4173' Bottom 4193' Total Depth of Well 4250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	335'	none
				5-1/2"	4248'	3320'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4220', ran sand to 4180', ran 5 sacks of cement.
Shot pipe at 3337 and 3308', got loose and pulled pipe. Set
rock bridge at 300' and ran 25 sacks of cement. Filled to 40',
set rock bridge and ran 10 sacks of cement on top. Racked unit
and tallied pipe.

PLUGGING COMPLETE.

COPY OF DRILLERS LOG ATTACHED.

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 67

My commission expires February 15, 1971

Margaret Melcher
Notary Public.

15-095-01086-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: GULF OIL COMPANY
Farm: R. S. Reida No. 2

SEC. 19 T. 30 R. 6W
SW NE SE

Total Depth: 4251'
Comm. 3-13-61 Comp. 3-24-61
Shot or Treated.
Contractor, Garvey Drlg.
Issued. 7-22-61

County Kingman
KANSAS



Elevation, 1487' DF

Production, 24 BOPD

Figures Indicate Bottom of Formations.

surface soil & red bed	45
red bed	337
red rock & shale	700
shale & lime	1220
lime & pyrite	1305
shale & lime	1370
lime & shale	1780
shale & lime	2880
soft lime	2940
lime	3045
lime & shale	3285
shale	3460
lime & shale	3650
shale & lime	3725
lime	3934
lime & shale	3977
lime	4059
shale & lime	4172
Mississippi chert	4195
Mississippi chert & lime	4251
Total Depth	

TOPS: SCOUT	
Heebner	3102
Douglas Shale	3195
Lansing	3339
Kansas City	3615
Mississippi	4173

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1967
CONSERVATION DIVISION
Wichita, Kansas

15-095-01086-0000

313

LOG WORK SHEET AND WELL RECORD
GULF DPD-367

OPERATOR Gulf Oil Corporation		LEASE R. S. Reida			WELL 2
POOL South Reida	DISTRICT-AREA Wichita Area	SEC..TWP..RGE. 19-30S-6W	COUNTY Kingman	STATE Kansas	CLASSIFICATION Proven-Dev.
DATE OF REPORT 5-17-61	DATE DROPPED FROM REPORT 5-16-61	DATE DRILLING BEGAN 3-13-61	DATE WELL COMPLETED 4-15-61	INDICATED CAPACITY	GRAVITY
DISTANCE IN 12'	TOTAL DEPTH 4250'	PLUG BACK TOTAL DEPTH 4220'	K. B. ELEVATION Gr. Elev. 1480'	D. F. ELEVATION 1490'	TOP OF CEMENT BEHIND CASING

INITIAL PRODUCTION: State Test 5-15-61 - 40 BO, 230 BW, 24 hrs.

FORMATION AND PRODUCING INTERVALS: Miss. - 4193'

1650' NSL, 990' WEL

RECEIVED	NOV 27 1961
----------	-------------

CASING RECORD

SIZE	WT.	THD.	COND.	MAKE	SET AT	SACKS CEMENT	POUNDS CAL. CHLO.	CASING TALLIES
8 5/8"	28#	10 V	B	LW	335'			323'
Cmt'd by HOWCO w/100 sx reg Victor mixed w/16% bentonite, 4% NaCl followed by 30 sx regular Victor w/3% CaCl.								
5-1/2"	14#	8RT	A	J55	4248'			4236'
Cmt'd w/150 sx Class A cmt. cont. 1% Halad #9 and 2% Cacl.								

RECORD OF SHOWS, FRACTURES AND ACID JOBS *

Sec. 19-30S-6W Kingman County, Ks.

Notched casing at 4193' w/SW and 3,000# 20-40 sd. Treated w/250 gal Mud Sol Acid.
Frac'd w/75/gelled lease crude cont 0.1 ppg Mark II. Adpmite and 4000# 10-20 sd in 2' stg.

OPERATOR Gulf Oil	INTEREST 100%	OBJECTIVE HORIZON Mississippi	EST. TOTAL DEPTH 4175'
PARTNER	INTEREST	AFE D&C ET# 18103	DATE APPROVED 2-24-61
PARTNER	INTEREST	LEASE NO. 66655	TOTAL AMOUNT \$42,000
PARTNER	INTEREST	CONTRACTOR Garvey Drilling Co., Wichita, Kansas	GULF INTEREST 100%
PARTNER	INTEREST	SURVEY LETTER	DRILLING PERMIT NO.

OUTSIDE FORMS	NOTICE OF INTENTION TO		DATE SUBMITTED		
	DRILL	PLUG	WELL RECORD	PLUGGING RECORD	ELECTRIC LOG
() STATE					
() FEDERAL					
() OSAGE					
() SCHOOL					

* SEE REVERSE SIDE FOR WORK SUBSEQUENT TO DRILLING