


15-095-00283-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

KINGMAN County. Sec. 19 Twp. 30 Rge. 6 (X) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner PETROLEUM, INC.
Lease Name KALIVODA Well No. 11
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed November 2, 19 57
Application for plugging filed February 14, 19 58
Application for plugging approved February 17, 19 58
Plugging commenced March 28, 19 58
Plugging completed April 2, 19 58
Reason for abandonment of well or producing formation No producible zones
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel, Pretty Prairie, Kansas
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4192 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Mississippi</u>	<u>Water with a rainbow of oil</u>	<u>4140'</u>	<u>4148'</u>	<u>8-5/8"</u> <u>4-1/2"</u>	<u>309'</u> <u>4260'</u>	<u>None</u> <u>3280'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with crushed rock from 4192' to 4077' and placed 4 sacks cement on top of rock. Mudded up to 270' and made solid rock bridge on top of mud. Placed 20 sacks cement on to rock bridge and mud up to 20', filled hole to base of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service
Address 102 West 18th Street, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Don Searle (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 19 58

My commission expires July 11, 1960

John J. Brown
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 19 T. 30 R. 6
BOOK PAGE 82 LINE 32

APR 9 1958
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 19 T. 30S R. 6W

FARM KALIVODA

NO. 1

LOC. NW, NW, NE


TOTAL DEPTH 4545'

COUNTY Kingman Co., Kansas

COMM. October 8, 1957

COMP. October 24, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 309' W/250 sax.
4 1/2" @ 4260' W/175 sax.

ELEVATION 1562' DF

PRODUCTION Plugged & Abandoned

FIGURES INDICATE BOTTOM OF FORMATIONS

100	Sand & red rock
310	Red rock, red bed & shale
1030	Shale & shells
1100	Shale W/lime streaks
1615	Lime
2133	Shale & lime
2280	Shale
2943	Lime & shale
3033	Sand, lime & shale
3189	Lime & shale
3283	Shale & sand
3430	Lime
3652	Lime & shale
3737	Lime
3749	Cherty lime
3810	Lime
4130	Shale & lime
4315	Chert
4344	Lime
4372	Chert & lime
4414	Lime & shale
4471	Shale
4503	Shale & lime
4525	Shale
4545	Simpson sand
4545	T. D.

RECEIVED
STATE CORPORATION COMMISSION

APR 9 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
SEC. 19 T. 30 R. 6W
BOOK PAGE 82 LINE 32

State of KANSAS }
County of BARTON } ss:

I, Verne A. Morris of Garvey Drilling co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Kalivoda well

Verne A. Morris

Subscribed and sworn to before me this 13th day of November 19 57

My Commission Expires: July 11, 1960

Notary Public Signature
NOTARY PUBLIC