

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

# WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Kingman County, Section 11, Twp. 29, R. 19  
 Location as "NE (CNW) SW" or footage from line: NE NE SE  
 Lease Owner: Pickrell Drilling Company  
 Lease Name: Piesmever  
 Office Address: 705 1/2 W. National Bank Bldg., Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole  
 Date well completed: January 6, 1957  
 Application for plugging filed: January 6, 1957  
 Application for plugging approved: January 6, 1957  
 Plugging commenced: January 6, 1957  
 Plugging completed: January 6, 1957  
 Reason for abandonment of well or producing formation: SD&A

If a producing well is abandoned, date of last production: \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: M. A. Rives  
 Producing formation: \_\_\_\_\_ Depth to top: \_\_\_\_\_ Bottom: \_\_\_\_\_ Total Depth of Well: 1735 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	DEPTH	REMOVED OUT
				8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filed with heavy mud to 200' bridge hole and cemented with 20 sacks cement. Then heavy mud to 20' below cellar bridge hole and cement with 15 sacks to bottom of cellar.

Name of Plugging Contractor: Pickrell Drilling Company  
 Address: 705 1/2 W. National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick  
 I, \_\_\_\_\_ (employee or owner) of town of \_\_\_\_\_ of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts stated and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So helping God.  
 Signature: \_\_\_\_\_  
 Pickrell Drilling Co., 705 1/2 W. Nat'l. Bank Bldg.

SUBSCRIBED AND SWORN to before me this 13th day of January, 1957.  
 My commission expires July 30, 1958  
 Notary Public.

PLUGGING  
 CONSERVATION DIVISION  
 FILE SEC. 1, Wichita, Kansas  
 BOOK PAGE 132, LINE 9

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company, etal  
Wichita, Kansas

Rotary Drilling Commenced 12/19/56

Rotary Drilling Completed 1/7/57

LOCATION: NE NE SE Sec. 1-29-9, Kingman County, Kansas

Tiesmeyer #1

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: 200' (5 jts.) 8 5/8" 22.7# Armco Spiralweld Casing set at 200' with 150 sacks cement circulated.

Filled with heavy mud to 200', bridge hole and cemented with 20 sacks cement. Then heavy mud to 29' below cellar, bridge hole and cement with 15 sacks to bottom of cellar.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Clay	25	Circ. for samples at	3925
Sand	40		3935
Clay & Sand	200		3945
Red Bed & Shale	1005		4190
Salt, Shale & Shells	1365		4205
Lime & Shale	1595		4215
Lime	2040		4480
Lime & Shale	2305		4524
Shale & Shells	2650		4529
Lime & Shale	2895		4531
Lime	3235		4695
Shale	3297		
Shale & Lime	3365		
Shale, Sand & Lime	3452		
Sand & Lime	3554		
Lime & Shale	3605		
Lime	4085		
Lime & Shale	4164		
Lime	4195		
Mississippi	4335		
Lime & Shale	4390		
Shale	4457		
Lime & Shale	4500		
Shale	4520		
Viola Lime	4540		
Lime & Sand	4585		
Sand & Shale	4631		
Shale	4685		
Arbuckle	4735 T.D.		

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1957  
CONSERVATION DIVISION  
Wichita, Kansas

S.L.M. at 2000 - O.K.  
3000 - O.K.  
4000 - O.K.

Slope Test at 2500 - 0° off  
3000 - 0° off  
4000 - 0° off

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports

PLUGGING  
FILE SEC 1 T 29 R 9 W  
BOOK PAGE 132 LINE 9

PICKRELL DRILLING COMPANY  
By: [Signature] Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 11th day of January, 1957, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

[Signature] Notary Public