

15-095-20467-0000

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
State Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Kingman County, Sec 31 Twp. 28SRgc. NW 5 (W)
 Location as "NE/CNW/SE" or footage from lines NW NE SE
 Lease Owner Graves Drilling Co., Inc.
 Lease Name Adrian Well No. 1
 Office Address 910 Union Center, Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed April 5 19 76
 Application for plugging filed April 5 19 76
 Application for plugging approved April 5 19 76
 Plugging commenced April 5 19 76
 Plugging completed April 5 19 76
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 10
 Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas
 Producing formation Depth to top Bottom Total Depth of Well 3965 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205.35	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 200 feet. Followed by wooden plug and 1/2 sack hulls
 Placed 35 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed
 by wooden plug, 1/2 sack hulls and 15 sacks cement to base of well collar.
 Plugged rat hole with 2 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 12 1976
 CONSERVATION DIVISION
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Graves Drilling Co., Inc.
 Address 910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK 58.
 John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John C. Graves*
 910 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of April 19 76

My commission expires February 2, 1980
 Courtney M. Graves Notary Public.



15-095-20467-0000

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: 29 March 1976

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: 5 April 1976

CASING RECORD: 5 Jts. 217' of used 8-5/8"
cemented with 180 sacks

LOCATION: Adrian No. 1
Approx. NW NE SE
Section 31-28S-5W
Kingman County, Kansas

- 0 - 217 Red bed & shale
 - 217 - 1260 Sand & shale
 - 1260 - 1490 Shale & lime
 - 1490 - 1940 Shale & shells
 - 1940 - 2240 Shale
 - 2240 - 2675 Shale & shells
 - 2675 - 3190 Shale
 - 3190 - 3535 Shale
 - 3535 - 3690 Shale & lime
 - 3690 - 3875 Lime & shale
 - 3875 - 3965 Lime
- 3965 Rotary Total Depth

RECEIVED
STATE CONSERVATION COMMISSION
APR 12 1976
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By J. H. Graves
President

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 9th day of April, 1976

My commission expires: 2 February 1980

Courtney M. Graves
Courtney M. Notary Public
Graves

