

15-095-20536-0600


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 22 Twp. 28 Rge. 5 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NW NE NW

Lease Owner Maurice L. Brown
Lease Name Lindholm B#1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/18/76 _____ 19____
Plugging completed 12/22/76 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3940
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	261	none
				5 1/2"	3940	3076'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 3780' and set 5 sacks cement. Loaded casing with water, shot pipe at 3072',
pulled 78 joints. Set rock bridge at 250' and ran 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1977

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1976

Margaret Melcher
Notary Public.

My commission expires _____



DRILLERS LOG

OPERATOR Maurice L. Brown Company
 1500 Vickers KSB&T Building
 Wichita, Kansas 67202

LEASE Lindholm 'B' No.1
 NW NE NW Sec. 22-28-5W
 Kingman County, Kansas

CONTRACTOR Slawson Drilling Company, Inc.
 408 One Twenty Building
 Wichita, Kansas 67202

RTD 3940'

COMMENCED 10/19/76

COMPLETED 10/30/76

CASING 255.31' new 8-5/8" set at 261' with 250 sx cement

0' to 230' Lime & Shale
 230' to 1225' Lm & Shale
 1225' to 1590' Shale & Lime
 1590' to 2002' Lime & Shale
 2002' to 2325' Shale & Lm
 2325' to 3715' Lime & Shale
 3715' to 3800' Shale & Lime
 3800' to 3825' Lime
 3825' to 3840' Lime & Shale
 3840' to 3858' Miss Chert & Dol.
 3858' to 3940' Lime & Chert
 3940' RTD

STATE OF KANSAS

COUNTY OF SEDGWICK

I, Jim Thatcher, of the Slawson Drilling Company, Inc.
upon oath state that the above and foregoing is a true and correct copy
of the log of the Lindholm 'B' No.1 well.

JIM THATCHER


 JIM THATCHER

Subscribed and sworn to me on November 8th, 1976

Mary Lou Taylor

 Mary Lou Taylor, Notary

My commission expires January 17, 1977



RECEIVED
 STATE OF KANSAS COMMISSIONER
 DEC 02 1976
 GEORGE W. WILSON, D.P.S. 1
 Wichita, Kansas