


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-095-20536-0000 Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec. 22 Twp. 28S Rge. (X) 5 (W)
Location as "NE/CNW/SE/SW" or footage from lines NE SW NW
Lease Owner John C. Graves, National Oil, Transcon
Lease Name Lindholm Well No. 1
Office Address 505 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 12, 19 74
Application for plugging filed February 12, 19 74
Application for plugging approved February 12, 19 74
Plugging commenced February 12, 19 74
Plugging completed February 12, 19 74
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3865 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 200 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls, Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 22nd day of February, 19 74

My commission expires May 9, 1975
Betty Brandt
Betty Brandt Notary Public

15-095-20536-0000

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves, et al.
505 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: January 31, 1974

CONTRACTOR: Graves Drilling Co., Inc.
505 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: February 12, 1974

CASING RECORD: 5 Jts. 210' 8-5/8"
cemented with 160 sacks

LOCATION: Lindholm No. 1
NE SW NW
Section 22-28S-5W
Kingman County, Kansas

0 - 120	Rock	2660 - 2690	Sandy shale
120 - 210	Sandy Shale	2690 - 2797	Shale
210 - 225	Lime	2797 - 2985	Shale & lime
225 - 528	Shale	2985 - 3002	Sandy shale
528 - 912	Shale & shells	3002 - 3437	Lime
912 - 1202	Shale & lime streaks	3437 - 3585	Shale
1202 - 1455	Lime & shale	3585 - 3738	Lime & shale
1455 - 1795	Lime with shale	3738 - 3800	Shale & lime
1795 - 2070	Lime & shale	3800 - 3830	Lime & chert
2070 - 2122	Sandy shale	3830 - 3835	Lime
2122 - 2440	Lime & shale	3835 - 3856	Chert
2440 - 2660	Lime & shale	3856 - 3865	Lime
		3865	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1974

CONSERVATION DIVISION
Wichita, Kansas

By

John Graves

President

STATE OF KANSAS)

SEDGWICK COUNTY)

ss.

Subscribed and sworn to before me, a Notary Public, this 22nd of February, 1974.

My commission expires: May 9, 1975

Betty Brandt
Betty Brandt

Notary Public