


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-095-015416-0000

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec. 22 Twp. 28S Rge. (E) 5 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW NW
Lease Owner Beardmore Drilling Company
Lease Name Lindholm B Well No. 1
Office Address 603 Petroleum Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed May 10 19 52
Application for plugging filed May 10 19 52
Application for plugging approved May 10 19 52
Plugging commenced May 10 19 52
Plugging completed June 12 19 52
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 3860 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	125	8- $\frac{3}{8}$	125	None
		0	3826	5- $\frac{1}{2}$	3826	3102

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Hole was cement to 3800'. Shot pipe off at 3099'.
Pulled pipe and mudded hole to 160'. Set rock bridge
and dumped 25 sacks of cement at 160'. Finished
mudding hole and dumped 5 sacks cement at top of surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mr. Bert Self
Address 419 E. 6th, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, Heber Beardmore, (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
603 Petroleum Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of June, 19 52
Notary Public.

My commission expires January 28, 1956

PLUGGING
FILE SEC 24 28 52
BOOK PAGE 23 LINE 41

RECEIVED
CORPORATION COMMISSION
JUN 21 1952
CONSERVATION DIVISION
Wichita, Kansas

15-095-01546-0000

Lindholm B #1

NW NW NW
Section 22-28S-5W
Kingman County, Kansas

Drilled for: Beardmore, et al
Drilled by: Beardmore Drilling Company

Casing Record:

8-5/8" 125' w/100 Sacks Cement
5-1/2" 3826' w/50 Sacks Cement

Date Commenced: April 19, 1952
Date Completed: May 10, 1952

Elevation: 1392 DF
1390 GR
1395 RB

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Clay Sand	70
Shale - Shells	865
Lime Broken	1245
Lime	1310
Shale - Shells	1965
Shale - Lime	2990
Lime Broken	3300
Lime	3836 T.D. (Rotary)
Lime - Chat	3860 T.D. (Cable)

D & A

TOPS:

Lansing	3008
Mississippi	3798
Dolomite	3826

DST #1 - 3826-3834 - Open 1 hour, shut in 15 minutes
good blow. Dropped drill pipe and tester in hole.
Best estimate 60' slightly oil cut mud. BHP#390#.

DST #2 - 3826-3836 T.D. - Open 1 hour, 10 minutes, Shut in
20 Minutes good blow. Recovered 50' gas cut mud, 110'
very slight oil cut mud, 40' water and 1 gallon free oil
in testing tool. BHP 680#.

STATE OF KANSAS

ss

COUNTY OF SEDGWICK


I, the undersigned, being duly sworn on oath state that the above and within
statement is a true and correct record and log of the well drilled on the location
above-described, to the best of my knowledge and belief.

John Beardmore

Subscribed and sworn to before me this 13th day of May, 1952.

Leonard P. Tolle
Notary Public

My Commission Expires: January 28, 1956



RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1952
CONSERVATION DIVISION
Wichita, Kansas