

API NUMBER 15-095-00704-0000

LEASE NAME Bolinger "A"

WELL NUMBER 1

330' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 21 TWP. 28S RGE. 5 (S or W)

COUNTY Kingman

Date Well Completed 12-7-50

Plugging Commenced 5-14-92

Plugging Completed 5-14-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S Main, Suite 500

PHONE (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation Mississippi Depth to Top _____ Bottom T.D. 3836'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	207	8-5/8"	207	None
		0	3807'	5-1/2"	3807'	700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 3750' and cap with 2 sacks of cement. Stretch & shoot 5-1/2" casing. Pull casing to 700' and spot 30 sacks of cement. Pull casing to 300' and circulate cement to surface. Pull remaining 300' of casing and top off cement. 60-40 Poz, 4% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address P.O. Box 1781624, Wichita, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S Main, Suite 500
Wichita, KS 67202



Subscribed and sworn to before me this 22 day of May, 1992
Deborah Ann Paulus
 Notary Public

