


15-095-00009-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Get All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 20 Twp. 28S Rge. 5W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SE  
Lease Owner Artnell Co.  
Lease Name Dewey Well No. 1  
Office Address Petroleum Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed July 9 1956  
Application for plugging filed July 9 1956  
Application for plugging approved July 9 1956  
Plugging commenced July 9 1956  
Plugging completed July 9 1956  
Reason for abandonment of well or producing formation oil in commercial quantities not found  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3926' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	153'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 150'. Set #1 plug with 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company  
Address 1005 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. J. Clappitt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Prime Drilling Company

(Signature) [Signature]  
L. J. Clappitt  
1005 Central Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of July, 19 56  
Dorlene May Notary Public.  
My commission expires Sept. 30, 1959

COMMISSION Notary Public.  
JUL 12 1956 7-12-56  
CONSERVATION DIVISION  
KANSAS

PLUGGING  
FILE SEC 20 T. 28 R. 5W  
BOOK PAGE 79 LINE 37

ROTARY DRILLING LOG

OPERATOR: Artnell Company  
DEWEY #1  
SW SW SE Sec. 20-28S-5W,  
Kingman County, Kansas

CONTRACTOR: Prime Drilling Company  
COMM: 6/25/56  
COMP: 7/9/56

Formations:

Soil & Shale	154'
Shale & Sand	400'
Shale & Shells	710'
Salt	820'
Shale & Shell	945'
Anhydrite	965'
Shale & Shells	1000'
Lime & Shale	1390'
Sand	1410'
Lime	1415'
Shale & Lime	1730'
Lime	1755'
Shale & Lime	3160'
Lime	3270'
Lime & Shale	3335'
Lime	3500'
Shale	3520'
Lime	3665'
Lime & Shale	3710'
Lime	3855'
Lime & Chert	3880'
Miss. Dolomite	3890'
Lime	3926'
Rotary Total Depth (D&A)	3926'

Remarks: Set 8-5/8" surface casing  
at 153' cemented with 140 sacks Pozmix,  
2% C.C.

We certify the above log is true and  
correct to the best of our knowledge  
and belief.

PRIME DRILLING COMPANY

*R.R. McNicol*  
R. R. McNicol

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1956  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 20 T 28 R 5W  
BOOK PAGE 79 LINE 37