


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

KINGMAN County. Sec. 17 Twp. 28S Rge. (E) 5 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SW
Lease Owner HUBER & PABCO
Lease Name VINEY Well No. I
Office Address WICHITA KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DH
Date well completed 11-1-50 19
Application for plugging filed 11-5-50 19
Application for plugging approved 11-5-50 19
Plugging commenced 11-5-50 19
Plugging completed 11-9-50 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well RUEL DURKEE
Producing formation Depth to top Bottom Total Depth of Well 3895 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug back with crushed rock to 3835. Run 6 sx cement from 3835 to 3800. Fill with mud from 3800 to 150. Bridge solid with rock from 150 to 145. Run 15 sx cement from 145 to 115. Fill with mud from 115 to 20. Cap with 5 sx cement from 20 to cellar. Pull 3492 of 5 1/2 csg., 8 5/8 csg left cemented in.

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1950

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Pabco drilling, Inc.
Address 818 Central Building
Wichita Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
D. J. BRIGGS (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. J. Briggs
D. J. BRIGGS
WICHITA KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of NOVEMBER, 19 50
Ruth M. Gaidner
Notary Public.

My commission expires March 2, 1953

PLUGGING
FILE SEC 17 T 28 R 5W
BOOK PAGE 43 LINE 15

15-095-00218-0000

DRILLER'S LOG

COMPANY: Huber & Pabco
CONTRACTOR: Pabco Drilling, Inc.

LOCATION: SE SE SW 17-28S-5W
Kingman County, Kansas

FARM NAME: No. 1 Viney

PRODUCTION: DRY & ABANDONED

COMMENCED: 9-30-50
COMPLETED: 10-14-50

CASING USED: 8 5/8" at 150' with 125 sacks cement
5 1/2" at 3882' with 25 sacks cement

Shale & shells 150
Shale & shells 690
Lime 935
Salt & shale 980
Shale & lime 1125
Lime 2660
Lime & shale 2765
Lime 3128
Lime & shale 3523
Lime 3850
Total depth 3895

SAMPLE TOPS:

Brown Limestone 2982
Mississippian 3837

D.S.T. 3837-50, open 1 1/2 hours, recovered 68' of very slightly oil & gas cut mud, no bottom hole pressure.

D.S.T. 3852-87, gas to surface in 23 minutes, open 1 hour, recovered 300' very gassy mud, slightly oil cut. Bottom hole pressure 630#/15 minutes.

D.S.T. 3882-95 total depth, open 1 hour, recovered 150' of oil cut mud.
5 1/2" at 3882 with 25 sacks cement.

Drilled plug and cleaned out to rotary depth, swabbed off water load and tested 2 barrels oil plus 2 barrels water/7 hours. Small show gas.

Acidized with 500 gallons, swabbed 35 barrels water and 15 barrels oil/15 hours; 25 barrels water plus 1 barrel oil/14 hours.

Acidized with 2500 gallons of 15% acid. Tested 65 barrels water plus 2 barrels oil/18 hours.

Perforated 96 shots 3851-75 with a jet gun, swabbed 26 barrels water plus 1 1/2 barrels oil 26 hours. DRY & ABANDONED.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1950
CONSERVATION DIVISION

I, Edward A. Huffman, hereby certify that the above is a true and correct copy of the log of the #1 Viney, located in the Southeast Quarter of the Southeast Quarter of the Southwest Quarter (SE SE SW) of Section Seventeen (17), Township Twenty-eight (28) South, Range Five (5) West, Kingman County, Kansas.

Edward A. Huffman
Edward A. Huffman, District Manager
J. M. HUBER CORPORATION

SUBSCRIBED & SWORN to before me this 28 day of November, 1950.

Dorothy J. Reeves
Notary Public

My Commission expires: January 26, 1953.