

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-21,438-0000

LEASE NAME Ralph

WELL NUMBER 1

SPOT LOCATION S/2 SE NE

SEC. 17 TWP. 28 SRGE. 5 (E) or (W)

COUNTY Kingman

Date Well Completed 3-16-84

Plugging Commenced 5-3-84

Plugging Completed 5-3-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Graves Drilling Co., Inc.

ADDRESS 910 Union Center, Wichita, Kansas 67202

PHONE # (316) 265-7233 OPERATORS LICENSE NO. 5428

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 2

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	227'	None
				5-1/2"	3899'	2957'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set. Plug set @ 3816', Perforations from 3806' to 3812'. Dump 60 gallons of sand & 30 barrels of water to plug back perforations. Let fall to bottom. Dump 5 sacks common cement on bottom. Buie Co. pumped in 2 sacks hulls & 120 sacks of 60-40 posmix, 2% Gel, 3% CC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor The Buie Co. License No. 9507

Address 1500 KSB&T Building, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Betty Brandt

(employee of operator)

(operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Betty Brandt

(Address) 910 Union Center
Wichita, Kansas 67202



SUBSCRIBED AND SWORN TO before me this 18th day of June, 1984

Tricia K. Glidewell
Notary Public

My Commission expires: March 16, 1986

RECEIVED
STATE CORPORATION COMMISSION
AUG 07 1984
CONSERVATION DIVISION
Wichita, Kansas