

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.C.R.-62-3-117

API NUMBER 15-095-21831-0000

LEASE NAME Dalton

WELL NUMBER 1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 17 TWP. 28 RGE. 5 (E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 8-11-03

Plugging Completed 8-13-03

SEP 04 2003

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Bear Petroleum, Inc.

ADDRESS P.O. Box 438, Haysville, KS 67060

PHONE (316) 524-1225 OPERATORS LICENSE NO. 4419

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-16-03 (date)

by Luthy (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? yes

Producing Formation Mississippi Depth to Top 3746 Bottom 3756 T.D. 3890

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	Surface	229	8 5/8	229	0
	Production	Surface	3889	4 1/2	3889	1970

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom back to 3620', dump bailed 4 sax cement, ripped pipe at 1970', pulled to 850' FS, spotted 35 sax, pulled to 450', spotted 35 sax, pulled to 280', circulated cement to surface.

Total 350 sax 60/40 Poz.

Name of Plugging Contractor Mikes Testing & Salvage License No. 31529

Address P.O. Box 467, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bear Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. A. Schremmer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 438, Haysville, KS 67060

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 19 2003

Shannon Howland

Notary Public

My Commission Expires: 3-10-2004

SHANNON HOWLAND
Notary Public - State of Kansas
My Appt. Expires 3/10/04

STATE OF KANSAS
STATE CORPORATION COMMISSION
D. S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

15-095-21831-00-00
API NUMBER 15-095-2183-0000

LEASE NAME Dalton

WELL NUMBER A #1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 17 TWP. 28 RGE. 5W (E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 8-11-03

Plugging Completed 8-13-03

RECEIVED
AUG 26 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR BEAR PETROLEUM, INC.

ADDRESS P.O. Box 438 Haysville, Kansas 67060

PHONE(S) (316) 524-1225 OPERATORS LICENSE NO. 4419

Character of Well Oil

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	229'	None
				4-1/2"	3889'	1970'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from _____ feet to _____ feet each sack. Plugged off bottom with sand to 3620' and 4 sacks cement. Shot casing @3020', pipe parted @1970'. Pulled up to 850', pumped 35 sacks cement, pulled up to 450', pumped 35 sacks cement, pulled up to 280' and circulated cement to surface, 60/40 pos, 4% gel. Layed rest of pipe down. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of August, 20 03

My Commission Expires: _____



Notary Public